

[illegible]

Sargent Drilling
INDUSTRIAL ENGINEERING
COMPLETE MUNICIPAL AND INDUSTRIAL
WELL AND PUMP SERVICE

PO Box 367
Geneva, NE 68361-0367

846 South 13th St.

Phone: (402) 759-3902
1-888-496-3902

TEST HOLE LOG

CUSTOMER: City of Wichita	
WELL ID: OB6S	
LOCATION: SW ¼ SW ¼ SW ¼ SW ¼, 32-T23S-R2W, Harvey Co., KS	
LATITUDE: 38° 00' 00.4"	
LONGITUDE: 097° 34' 23.0"	
FOOTAGES: 214 feet from the South section line and 5103 feet from the East section line.	
DATE: 10-22-09	DRILLED BY: CL

SWL:
PWL:

from feet - to feet

0	14	Topsoil and clay
14	40	Fine, medium and coarse sand
40	50	Fine, medium and coarse sand and fine gravel

Well Depth: 50'
Bore Hole Dia: 6"

Plain casing: 40' of 2"
Perf. casing: 10' of 2"

slot size: .020"

Gravel pack from 35' to 50'
Bentonite from 0' to 35'

dh