

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: EDWARDS SW 1/4 SW 1/4 SW 1/4 5 T 23 S R 20 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM OPFERLE - 7 1/2 N, 2 E, 6 N, 1/2 W AND 3/4 SOUTH

2 WATER WELL OWNER: D & D PUMP INC.
 RR#, St. Address, Box #: 56 HIGHWAY WEST Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SUBLETTE, KS 67877- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 265 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 133 ft. below land surface measured on no/day/yr 07/13/06
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 25 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 265 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

	NW	NE
SW		SE

5 TYPE OF BLANK CASING USED: CERTA LOC CASIM CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 265 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 200 ft. to 260 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 22 ft. to 265 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 0 ft. to 22 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? NORTHEAST How many feet? 20

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	40	01 TOPSOIL 32 TAN CLAY			
40	80	36 BLUE CLAY			
80	140	32 TAN CLAY			
140	160	16 GRAY CLAY 29 SANDSTONE			
160	180	29 SANDSTONE 16 GRAY CLAY 26 RED CLAY			
180	200	16 GRAY CLAY 26 RED CLAY 29 SANDSTONE			
200	265	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (no/day/year) 07/14/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 07/26/06 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Judith Critt*