

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: FORD SE 1/4 SE 1/4 SE 1/4 19 T 25 S R 22 **EW** (DRL)

Distance and direction from nearest town or city street address of well if located within city?
 FROM SPEARVILLE - 1 1/2 WEST ON EAGLE RD.

2 WATER WELL OWNER: GLEASON, RICHARD Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: BOX 266 - 12496 EAGLE RD. Application Number:
 City, State, ZIP code: SPEARVILLE, KS 67876-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 128 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 66 ft. below land surface measured on mo/day/yr 09/15/10
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 35 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 128 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CERTA LOC CASIM CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 128 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 60 ft. to 120 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 30 ft. to 128 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout Intervals: From 5 ft. to 30 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? EAST How many feet? 15

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY			
20	40	32 TAN CLAY 14 WHITE CLAY 35 CALACHIE			
40	60	35 CALACHIE 27 ROCK 02 FINE SAND			
60	80	02 FINE SAND 24 THINROCLAYER			
80	100	10 FINE-MEDSAND 24 THINROCLAYER 16 GRAY CLAY			
100	120	16 GRAY CLAY 27 ROCK 16 GRAY CLAY			
120	180	16 GRAY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 09/16/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 09/20/10 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Cuck*