

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HODGEMAN SE 1/4 NW 1/4 SE 1/4 31 T 23 S R 21 E

Distance and direction from nearest town or city street address of well if located within city?
 FROM HANSTON - 7 SOUTH, 3 EAST, 172 SOUTH AND 172 EAST

2 WATER WELL OWNER: ROSEMARY HERRMAN & HEISS
 RR#, St. Address, Box #: P.O. BOX 295 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: KINSLEY, KS 67547- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 297 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 106 ft. below land surface measured on no/day/yr 09/10/93
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 297 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, no/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 297 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 253 ft. to 293 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 55 ft. to 297 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
 Grout intervals: From 0 ft. to 55 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE - NEW SITE
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	TOPSOIL FINE SAND BLUE SHALE			
20	40	BLUE SHALE			
40	60	BLUE SHALE GRAY CLAY			
60	80	GRAY CLAY SANDSTONE			
80	110	SANDSTONE			
110	120	GRAY CLAY			
120	190	SANDSTONE			
190	192	ROCK LAYERS			
192	200	GRAY CLAY			
200	220	GRAY CLAY THIN ROCK LAYER			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (no/day/year) 09/13/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (no/day/yr) 09/17/93 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Aick*

(Continued) WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HODGEMAN SE 1/4 NW 1/4 SE 1/4 31 T 23 S R 21 E

2 WATER WELL OWNER: ROSEMARY HERRMAN & HEISS
 RR#, St. Address, Box #: P.O. BOX 295 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: KINSLEY, KS 67547- Application Number:

FROM	TO	LITHOLOGIC LOG
220	240	GRAY CLAY RED CLAY
240	250	GRAY CLAY ROCK
250	287	SANDSTONE
287	0	ROCK LAYERS