

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: HODGEMAN SW 1/4 NE 1/4 SW 1/4 12 T 23 S R 23 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM JETMORE SOUTH ON HIGHWAY 283 - 3/4 E, 2 S AND 8 EAST

2 WATER WELL OWNER: STONE POST DAIRY  
 RR#, St. Address, Box #: ROUTE #1 - BOX 17D Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: JETMORE, KS 67854- Application Number: 15,359

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 285 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 142 ft. below land surface measured on mo/day/yr 10/28/06  
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 220 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 14 in. to 285 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: INDUSTRY  
 Was a chemical/bacteriological sample submitted to department? No;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: CASING JOINTS: CLAMPED  
 Blank casing diameter 8 in. to 285 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 21  
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC  
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 160 ft. to 280 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 72 ft., From 0 ft. to 0 ft.  
 From 88 ft. to 285 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE  
 Grout Intervals: From 5 ft. to 25 ft., From 72 ft. to 88 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: ABANDONED WELL  
 Direction from well? SOUTH How many feet? 50

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	12	01 TOPSOIL 32 TAN CLAY			
12	40	37 FIN-COAR SAN 06 SMALL GRAVEL 08 ROCK LAYER			
40	60	32 TAN CLAY 16 GRAY CLAY			
60	100	16 GRAY CLAY 26 RED CLAY			
100	120	08 ROCK LAYERS 16 GRAY CLAY			
120	140	16 GRAY CLAY 26 RED CLAY 36 BLUE CLAY			
140	160	16 GRAY CLAY 36 BLUE CLAY			
160	180	16 GRAY CLAY			
180	200	16 GRAY CLAY 29 SANDSTONE 19 LAYERS			
200	280	29 SANDSTONE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/29/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 11/17/06 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Jessie Creek*

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: HODGEMAN	SW 1/4 NE 1/4 SW 1/4	12	T 23 S	R 23 W

2 WATER WELL OWNER:	STONE POST DAIRY	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	ROUTE #1 - BOX 17D	Application Number: 15,359
City, State, ZIP code :	JETMORE, KS 67854-	

FROM	TO	LITHOLOGIC LOG
280	320	29 SANDSTONE 16 GRAY CLAY 19 LAYERS

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/29/06 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 11/17/06 under the business name of JOB'S WELL SERVICE, INC. by (signature) *Judith Creek*