

WATER WELL RECORD Form WWC-5 KSA 82a-1212

LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: HODGEMAN SE 1/4 SE 1/4 NW 1/4 8 T 23 S R 23 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM JETMORE - 1 MILE EAST, 2 MILES SOUTH & 1/2 MILE EAST

WATER WELL OWNER: HERRMANN, GEORGE Board of Agriculture, Division of Water Resources
 PPA: St. Address, Box #: 12436 US HIGHWAY 400 Application Number:
 City, State, ZIP code: DODGE CITY, KS 67801-

LOCATE WELL'S LOCATION WITH AN 'X' IN SECTION BOX:

	X		

4 DEPTH OF COMPLETED WELL 548 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 178 ft. below land surface measured on mo/day/yr 11/21/08
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 30 gpm; well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 9 in. to 548 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

TYPE OF BLANK CASING USED: CERTA LOC CASIN CASING JOINTS: CERTA-LOC
 Blank casing diameter 5 in. to 548 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 200 lbs/ft. Wall thickness or gauge No. 17
 TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
 SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 320 ft. to 340 ft., From 0 ft. to 0 ft.
 From 460 ft. to 548 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 548 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

SPROUT MATERIAL BENTONITE
 Grout Interval(s): From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: ABANDONED WELL
 Direction from well? WEST How many feet? 10

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	20	01 TOPSOIL 32 TAN CLAY 21 LIMESTONE			
20	40	21 LIMESTONE 32 TAN CLAY 07 BLUE SHALE			
40	160	07 BLUE SHALE 08 ROCK LAYERS			
160	180	36 BLUE CLAY 08 ROCK LAYERS			
180	240	16 GRAY CLAY 24 THINROCLAYER			
240	260	16 GRAY CLAY 29 SANDSTONE			
260	320	16 GRAY CLAY			
320	340	16 GRAY CLAY 29 SANDSTONE			
340	360	29 SANDSTONE			
360	380	29 SANDSTONE 16 GRAY CLAY			

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/yr) 11/22/08 and this record is true to the best of my knowledge and belief. Kansas water well Contractor's License No. 179 This Water well Record was completed on (mo/day/yr) 01/15/09 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Juliet Crick*

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: HODGEMAN	SE 1/4 SE 1/4 NW 1/4	8	T 23 S	R 23 W

2 WATER WELL OWNER:	HERRMANN, GEORGE	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	12436 US HIGHWAY 400	Application Number:
City, State, ZIP code :	DODGE CITY, KS 67801-	

FROM	TO	LITHOLOGIC LOG
380	470	16 GRAY CLAY
470	550	29 SANDSTONE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/22/08 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 179 This Water Well Record was completed on (mo/day/yr) 01/15/09 under the business name of JOE'S WELL SERVICE, INC. by (signature) *Judith Creek*