

OFFICE USE ONLY

↑

20

SEC

TEST HOLE REPORT

LAYNE Western, a Div. of
LAYNE Christensen
Wichita, Kansas

Contract Name: Wichita ASR	Test Hole No. RRW 1 MS (d)
	Date: August 16, 2006
	Driller: Kevin Holub

Location of Test Hole:	Elevation of Test Hole:
	Static Water Level:
	Measured Hours After Completion

From	To	Description of Strata
0	5	brown silty sand, fine
5	10	red-orange silty sandy, fine
10	15	red orange silty sand, fine, slightly clay
15	20	red clayey silty sand, fine
20	25	red silty sand, fine, slight clay
25	30	red silty clayey sand, fine
30	35	light red, sandy silty clay, low plastic
35	40	light red, silt clay, low to medium plastic, slight sand
40	45	light red, olive, silty clay, medium to high plastic
45	50	olive silty clay, medium to high plastic
50	55	olive silty clay, medium to high plastic
55	60	olive silty clay, medium plastic
60	65	olive silty clay, medium plastic, slight sand
65	70	olive sand, fine to coarse clay lens
70	75	olive clayey silty sand, fine to coarse
75	80	olive sand, fine to coarse, slight clay
80	85	olive sand, fine to coarse
85	90	olive sand, fine to coarse
90	95	olive sand, very fine to coarse
95	100	olive sand, very fine to medium
100	105	olive sandy fine to coarse to olive gray shale