

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 028 FINNEY NE 1/4 NE 1/4 SE 1/4 29 T 23 S R 30 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM GARDEN CITY; APPX 2 MILES NORTH & 10 3/4 MILES EAST

2 WATER WELL OWNER: BRUCE ALGRIM
 RR#, St. Address, Box #: 2108 COMMANCHE Board of Agriculture, Division of Water Resources
 City, State, ZIP code: GARDEN CITY, KS 67846-3812 Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

/ \				
1	---	NW	---	NE
M				
i	W			X
l				
e				
\ /		SW		SE

4 DEPTH OF COMPLETED WELL 180 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 101 ft. below land surface measured on mo/day/yr 07/14/04
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 10 in. to 180 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 180 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 140 ft. to 180 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 180 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	21	04 SANDY CLAY			
21	64	31 CALICHE 20 LIMESTONE			
64	67	04 SANDY CLAY			
67	69	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
69	139	05 SAND 13 FINE GRAVEL 01 CLAY			
139	140	01 CLAY			
140	160	04 SANDY CLAY 05 SAND			
160	168	05 SAND			
168	189	31 CALICHE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/15/04 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04
 under the business name of HENKLE DRILLING & SUPPLY by (signature) -

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction NE 1/4 NE 1/4 SE 1/4	Section Number 29	Township Number T 23 S	Range Number R 30 W
---	----------------------------------	----------------------	---------------------------	------------------------

2 WATER WELL OWNER: RR#, St. Address, Box # : 2108 COMMANCHE City, State, ZIP code : GARDEN CITY, KS 67846-3812	BRUCE ALGRIM Board of Agriculture, Division of Water Resources Application Number:
---	--

FROM 189	TO 200	LITHOLOGIC LOG 19 SHALE
-------------	-----------	----------------------------

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/15/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04 under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce J. Richmond