


WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Finney	Fraction ¼ SW ¼ SE ¼ SE ¼	Section Number 19	Township No. T 23 S	Range Number R 32 <input type="checkbox"/> E <input checked="" type="checkbox"/> W
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here <input checked="" type="checkbox"/> .		Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: <input type="checkbox"/> WGS 84, <input type="checkbox"/> NAD 83, <input type="checkbox"/> NAD 27 Collection Method: <input type="checkbox"/> GPS unit (Make/Model:) <input type="checkbox"/> Digital Map/Photo, <input type="checkbox"/> Topographic Map, <input type="checkbox"/> Land Survey Est. Accuracy: <input type="checkbox"/> <3 m, <input type="checkbox"/> 3-5 m, <input type="checkbox"/> 5-15 m, <input type="checkbox"/> >15 m		
2 WATER WELL OWNER: Scott & Jill Ptacek RR#, Street Address, Box #: 5675 Koehn Avenue City, State, ZIP Code : Garden City, KS 67846				

3 LOCATE WELL WITH AN "X" IN SECTION BOX: N  S ----- mile-----	4 DEPTH OF COMPLETED WELL 300 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL 150ft. below land surface measured on mo/day/yr..... Pump test data: Well water was Airft. after Lift hours pumping..... gpm EST. YIELD 100 ...gpm. Well water was.....ft. after..... hours pumping..... gpm Bore Hole Diameter 10in. to 300ft., andin. toft. WELL WATER TO BE USED AS: <input type="checkbox"/> Public water supply <input type="checkbox"/> Geothermal <input type="checkbox"/> Injection well <input type="checkbox"/> Domestic <input type="checkbox"/> Feedlot <input type="checkbox"/> Oil field water supply <input type="checkbox"/> Dewatering <input type="checkbox"/> Other (Specify below) <input type="checkbox"/> Irrigation <input type="checkbox"/> Industrial <input checked="" type="checkbox"/> Domestic-lawn & garden <input type="checkbox"/> Monitoring well Was a chemical/bacteriological sample submitted to Department? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No If yes, mo/day/yr sample was submitted..... Water well disinfected? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
----------------------------------------------------------------------------------------------------------------------------------------------------------------------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

5 TYPE OF CASING USED: Steel PVC Other

CASING JOINTS: Glued Clamped Welded Threaded
 Casing diameter **.5**..... in. to **.260**..... ft., Diameter in. to ft., Diameter in. to ft.
 Casing height above land surface **.18**..... in., Weight **200**.....lbs./ft., Wall thickness or gauge No. **SDR21**.....
 TYPE OF SCREEN OR PERFORATION MATERIAL:
 Steel Stainless Steel PVC Other (Specify)
 Brass Galvanized Steel None used (open hole)
 SCREEN OR PERFORATION OPENINGS ARE:
 Continuous slot Mill slot Gauze wrapped Torch cut Drilled holes None (open hole)
 Louvered shutter Key punched Wire wrapped Saw cut Other (specify)
 SCREEN-PERFORATED INTERVALS: From **.260**..... ft. to **.300**..... ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From **.25**..... ft. to **.203**..... ft., From **.220**..... ft. to **.300**..... ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: Neat cement Cement grout Bentonite Other

Grout Intervals: From **.5**..... ft. to **.25**..... ft., From **203**..... ft. to **220**..... ft., From ft. to ft.
 What is the nearest source of possible contamination:
 Septic tank Lateral lines Pit privy Livestock pens Insecticide storage Other (specify below)
 Sewer lines Cesspool Sewage lagoon Fuel storage Abandoned water well
 Watertight sewer lines Seepage pit Feedyard Fertilizer storage Oil well/gas well
 Direction from well **South East**..... Distance from well **.65'**.....

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	2	Top Soil	200	203	Hard Cemented Sand
2	63	Brown Clay	203	220	Brown Clay, Few Small Sand Streaks
63	72	Fine to Medium Sand, Small Gravel	220	232	Medium to Coarse Sand, Small Gravel
72	86	Brown Clay			White Broken Rock
86	105	Brown Clay, Gypsum	232	247	Brown Clay
105	110	Medium to Coarse Sand, Small Gravel	247	277	Coarse Sand, Small Gravel, White
110	140	Brown Clay, Cemented Sand Streaks			Broken Rock
140	188	Medium to Coarse Sand, Few Brown Clay Streaks	277	289	Brown Clay, Few Sand Streaks
			289	296	Medium to Coarse Sand, Small Gravel
188	200	Coarse Sand, Small Gravel (Loose)	296	300	Brown Clay

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed, reconstructed, or plugged under my jurisdiction and was completed on (mo/day/year) **6-22-15**..... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. **532**..... This Water Well Record was completed on (mo/day/year) **7-20-15**..... under the business name of **Midwest Well & Pump Inc.**..... by (signature) *[Signature]*

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at <http://www.kdheks.gov/waterwell/index.html>.