

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 028 FINNEY SW 1/4 SW 1/4 SE 1/4 04 T 23 S R 33 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM GARDEN CITY; APPX 5 3/4 MILES NORTH & 3 MILES WEST

2 WATER WELL OWNER: RAY BAIER
 RR#, St. Address, Box # : RT 2 BOX 78 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : HOLCOMB, KS 67851-9803 Application Number:

3 LOCATE WELL'S LOCATION WITH
 AN "X" IN SECTION BOX:

/ \					
1	---	NW	---	NE	---
M	W				E
i					
l					
e					
		SW		SE	
\ /			X		

4 DEPTH OF COMPLETED WELL 238 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 128 ft. below land surface measured on mo/day/yr 08/11/04
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 11 in. to 238 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: OTHER JNT - CERTI-LOK
 Blank casing diameter 6 in. to 238 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 4 lbs/ft. Wall thickness or gauge No. .316
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 158 ft. to 218 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 238 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	17	01 CLAY 31 CALICHE			
17	31	01 CLAY			
31	42	07 FINE SAND 08 MEDIUM SAND			
42	68	01 CLAY 36 GYP ROCK 20 LIMESTONE			
68	81	01 CLAY			
81	97	01 CLAY 20 LIMESTONE			
97	104	20 LIMESTONE 01 CLAY			
104	120	01 CLAY			
120	141	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/19/04 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/05/04
 under the business name of HENKLE DRILLING & SUPPLY by (signature) -

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	SW 1/4 SW 1/4 SE 1/4	04	T 23 S	R 33 W

2 WATER WELL OWNER:	RAY BAIER	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RT 2 BOX 78	Application Number:
City, State, ZIP code :	HOLCOMB, KS 67851-9803	

FROM	TO	LITHOLOGIC LOG
141	151	01 CLAY
151	157	04 SANDY CLAY
157	178	05 SAND 13 FINE GRAVEL
178	184	01 CLAY
184	198	05 SAND
198	207	01 CLAY
207	218	07 FINE SAND 08 MEDIUM SAND 01 CLAY
218	231	01 CLAY 05 SAND
231	240	01 CLAY 20 LIMESTONE
240	247	31 CALICHE
247	260	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 08/19/04 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 11/05/04
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Richman*