

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	SW 1/4 SW 1/4 NW 1/4	16	T 23 S	R 33 W

Distance and direction from nearest town or city street address of well if located within city?  
 FROM HOLCOMB; APPX 4 3/4 MILES NORTH & 1 MILE WEST

2 WATER WELL OWNER: RAY BAIER  
 RR#, St. Address, Box #: RT 2 BOX 78  
 City, State, ZIP code: HOLCOMB, KS 67851-  
 Board of Agriculture, Division of Water Resources  
 Application Number: 999 & 1000

3 LOCATE WELL'S LOCATION WITH  
 AN "X" IN SECTION BOX:

/ \				
1	---	NW	---	NE
M	W	X		E
i				
l				
e				
		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL 344 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 138 ft. below land surface measured on mo/day/yr 11/08/04  
 Pump test data: Well water was 212 ft. after 4 hours pumping 1900 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 344 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 344 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 194 ft. to 234 ft.,	From 309 ft. to 339 ft.
	From 257 ft. to 287 ft.,	From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 344 ft.,	From 0 ft. to 0 ft.
	From 0 ft. to 0 ft.,	From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? NORTH How many feet? 86

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	20	01 CLAY 31 CALICHE			
20	37	05 SAND			
37	47	07 FINE SAND			
47	65	01 CLAY 36 GYP ROCK 05 SAND			
65	70	01 CLAY 20 LIMESTONE			
70	120	01 CLAY 20 LIMESTONE			
120	127	07 FINE SAND			
127	144	01 CLAY 05 SAND			
144	152	07 FINE SAND 01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/05/04 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/11/05  
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	SW 1/4 SW 1/4 NW 1/4	16	T 23 S	R 33 W

2 WATER WELL OWNER:	RAY BAIER	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RT 2 BOX 78	Application Number: 999 & 1000
City, State, ZIP code :	HOLCOMB, KS 67851-	

FROM	TO	LITHOLOGIC LOG
152	163	01 CLAY 05 SAND
163	172	07 FINE SAND
172	180	01 CLAY
180	182	05 SAND 13 FINE GRAVEL 14 MED GRAVEL
182	194	01 CLAY
194	224	05 SAND 01 CLAY
224	229	01 CLAY
229	234	05 SAND
234	245	01 CLAY 20 LIMESTONE
245	253	07 FINE SAND
253	258	01 CLAY
258	285	05 SAND 01 CLAY
285	312	01 CLAY
312	339	05 SAND 13 FINE GRAVEL
339	345	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/05/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/11/05 under the business name of HENKLE DRILLING & SUPPLY by (signature) <i>Berry Richmond</i>
---