

## WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction NW 1/4 NW 1/4 NE 1/4	Section Number 25	Township Number T 23 S	Range Number R 33 W
---	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?  
FROM GARDEN CITY; APPX 2 3/4 MILES NORTH

2 WATER WELL OWNER: CHARLES P. OLOMON JR TRST  
RR#, St. Address, Box #: 310 E. EMERSON AVE.  
City, State, ZIP code: GARDEN CITY, KS 67846-3132  
Board of Agriculture, Division of Water Resources  
Application Number: 1499 & 1500

3 LOCATE WELL'S LOCATION WITH  
AN "X" IN SECTION BOX:

/ \			X	
1	---	NW	---	NE
M				
i	W			E
l				
e				
		SW		SE
\ /				

4 DEPTH OF COMPLETED WELL 337 ELEVATION: 0  
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 118 ft. below land surface measured on mo/day/yr 04/10/06  
Pump test data: Well water was 146 ft. after 4 hours pumping 1315 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 337 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
Blank casing diameter 16 in. to 337 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 176 ft. to 236 ft., From 0 ft. to 0 ft.
	From 252 ft. to 332 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 337 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
What is the nearest source of possible contamination: NONE OBSERVED  
Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	24	01 CLAY			
24	33	10 V CRS SAND 14 MED GRAVEL			
33	34	01 CLAY			
34	46	09 COARSE SAND 13 FINE GRAVEL			
46	64	01 CLAY			
64	77	01 CLAY 05 SAND			
77	100	01 CLAY			
100	101	09 COARSE SAND 13 FINE GRAVEL			
101	122	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/31/06 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06  
under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NW 1/4 NW 1/4 NE 1/4	25	T 23 S	R 33 W

2 WATER WELL OWNER: CHARLES P. OLOMON JR TRST  
RR#, St. Address, Box # : 310 E. EMERSON AVE.  
City, State, ZIP code : GARDEN CITY, KS 67846-3132

Board of Agriculture, Division of Water Resources  
Application Number: 1499 & 1500

FROM	TO	LITHOLOGIC LOG
122	135	01 CLAY 09 COARSE SAND
135	142	09 COARSE SAND 13 FINE GRAVEL
142	156	01 CLAY 07 FINE SAND
156	164	09 COARSE SAND 13 FINE GRAVEL
164	174	08 MEDIUM SAND 01 CLAY
174	180	07 FINE SAND 05 SAND
180	226	08 MEDIUM SAND 09 COARSE SAND 13 FINE GRAVEL
226	230	05 SAND 28 ROCK
230	236	08 MEDIUM SAND 09 COARSE SAND 13 FINE GRAVEL
236	242	01 CLAY
242	250	01 CLAY 07 FINE SAND
250	257	07 FINE SAND 08 MEDIUM SAND
257	261	08 MEDIUM SAND 09 COARSE SAND
261	264	07 FINE SAND 08 MEDIUM SAND 01 CLAY
264	274	07 FINE SAND 08 MEDIUM SAND
274	284	08 MEDIUM SAND 09 COARSE SAND 13 FINE GRAVEL
284	294	07 FINE SAND 08 MEDIUM SAND 01 CLAY
294	304	09 COARSE SAND 13 FINE GRAVEL 28 ROCK
304	317	09 COARSE SAND 13 FINE GRAVEL
317	318	01 CLAY
318	324	09 COARSE SAND 13 FINE GRAVEL
324	332	09 COARSE SAND 01 CLAY
332	332	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/31/06 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/03/06  
under the business name of HENKLE DRILLING & SUPPLY by (signature)

*Bruno Reichmann*