

1 LOCATION OF WATER WELL: COUNTY: 028 FINNEY	Fraction SW 1/4 NW 1/4 SW 1/4	Section Number 25	Township Number T 23 S	Range Number R 34 W
---	----------------------------------	----------------------	---------------------------	------------------------

Distance and direction from nearest town or city street address of well if located within city?
FROM HOLCOMB; APPX 1 3/4 MILES NORTH & 3/4 MILE WEST

2 WATER WELL OWNER: THE GARDEN CITY COMPANY
RR#, St. Address, Box #: PO BOX 597
City, State, ZIP code: GARDEN CITY, KS 67846-0597
Board of Agriculture, Division of Water Resources
Application Number: FI 188

3 LOCATE WELL'S LOCATION WITH
AN "X" IN SECTION BOX:

1	---	NW	---	NE	---
M	---		---		---
i	W				E
l					
e	X	SW		SE	
	---		---		---

4 DEPTH OF COMPLETED WELL 332 ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 108 ft. below land surface measured on mo/day/yr 01/19/06
Pump test data: Well water was 201 ft. after 4 hours pumping 1658 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 24 in. to 332 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: 02 IRRIGATION

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
Blank casing diameter 16 in. to 332 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS:	From 230 ft. to 310 ft., From 0 ft. to 0 ft.
	From 317 ft. to 327 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS:	From 20 ft. to 332 ft., From 0 ft. to 0 ft.
	From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: 14 ABAND. WELL
Direction from well? SOUTHWEST

How many feet? 81

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	176	04 SANDY CLAY 20 LIMESTONE 05 SAND			
176	247	05 SAND 13 FINE GRAVEL 01 CLAY			
247	256	04 SANDY CLAY			
256	296	05 SAND 01 CLAY			
296	310	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
310	323	01 CLAY			
323	327	07 FINE SAND 08 MEDIUM SAND 28 ROCK			
327	333	31 CALICHE			
333	340	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/17/06 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 04/19/06
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Don J. Henkle*