

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number	
COUNTY: 028 FINNEY		NE 1/4 SW 1/4 SW 1/4		12		T 23 S		R 34 W	
Distance and direction from nearest town or city street address of well if located within city?									
FROM HOLCOMB; APPX 4 1/2 MILES NORTH & 3/4 MILE WEST									
2 WATER WELL OWNER:		TRIPLE G FARMS							
RR#, St. Address, Box # :		2150 ROAD 220		Board of Agriculture, Division of Water Resources					
City, State, ZIP code :		DEERFIELD, KS 67838-		Application Number: 5191					
3 LOCATE WELL'S LOCATION WITH				4 DEPTH OF COMPLETED WELL 344ELEVATION: 0					
AN "X" IN SECTION BOX:				Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.					
/ \				WELL'S STATIC WATER LEVEL 171 ft. below land surface measured on mo/day/yr 05/23/07					
				Pump testdata: Well water was 286 ft. after 4 hours pumping 859 gpm					
1 NW NE				Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm					
M				Bore Hole Diameter 24 in. to 344 ft., and in. to 0 ft.					
i W E				WELL WATER TO BE USED AS: 02 IRRIGATION					
1				Was a chemical/bacteriological sample submitted to department? No ;					
e				If yes, mo/day/yr sample was submitted Water well disinfected? Yes					
SW SE									
X									
/ \									
5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED									
Blank casing diameter 16 in. to 344 ft., Dia in. to 0 ft., Dia in. to 0 ft.									
Casing height above land surface 12 in., weight 37 lbs/ft. Wall thickness or gauge No. .219									
TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL									
SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT									
SCREEN PERFORATED INTERVALS: From 196 ft. to 236 ft., From 329 ft. to 339 ft.									
From 280 ft. to 300 ft., From 0 ft. to 0 ft.									
GRAVEL PACK INTERVALS: From 20 ft. to 344 ft., From 0 ft. to 0 ft.									
From 0 ft. to 0 ft., From 0 ft. to 0 ft.									
6 GROUT MATERIAL 03 BENTONITE									
Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.									
What is the nearest source of possible contamination: 14 ABAND. WELL									
Direction from well? NORTHEAST How many feet? 290									
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS									
0	2	02 SILT							
2	58	01 CLAY 05 SAND							
58	95	05 SAND 01 CLAY							
95	101	01 CLAY							
101	123	07 FINE SAND 08 MEDIUM SAND							
123	131	01 CLAY							
131	156	05 SAND 13 FINE GRAVEL 01 CLAY							
156	167	01 CLAY							
167	183	05 SAND 01 CLAY							
183	190	01 CLAY 05 SAND							
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/18/07 and this record is true to the best of my knowledge and belief. Kansas									
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/28/07									
under the business name of HENKLE DRILLING & SUPPLY by (signature)									

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 028 FINNEY	NE 1/4 SW 1/4 SW 1/4	12	T 23 S	R 34 W

2 WATER WELL OWNER: TRIPLE G FARMS

RR#, St. Address, Box # : 2150 ROAD 220

Board of Agriculture, Division of Water Resources

City, State, ZIP code : DEERFIELD, KS 67838-

Application Number: 5191

FROM	TO	LITHOLOGIC LOG
190	217	05 SAND 13 FINE GRAVEL
217	226	01 CLAY
226	236	05 SAND
236	282	01 CLAY 20 LIMESTONE
282	293	05 SAND
293	300	01 CLAY 05 SAND
300	325	01 CLAY 05 SAND
325	339	05 SAND
339	341	01 CLAY
341	350	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 05/18/07 and this record is true to the best of my knowledge and belief. Kansas

Water Well Contractor's License No. 145

This Water Well Record was completed on (mo/day/yr) 06/28/07

under the business name of HENKLE DRILLING & SUPPLY

by (signature)

Bruce R. Schmidt