

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: **047 KEARNY** NW 1/4 NW 1/4 NW 1/4 24 T 23 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM DEERFIELD, 1ME, 4 3/4 N TO WELL ON E SIDE

2 WATER WELL OWNER: HENRY BENTRUP-FRMRS NTNL
 RR#, St. Address, Box #: P.O. BOX 1611 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: GARDEN CITY, KS 67846- Application Number: 2715

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 368 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 170 ft. below land surface measured on mo/day/yr 07/17/96 Pump testdata: Well water was 236 ft. after 2 hours pumping 1115 gpm
Estimated Yield 1100 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
Bore Hole Diameter 24 in. to 38 ft., and in. to 0 ft.
WELL WATER TO BE USED AS: 02 IRRIGATION
Was a chemical/bacteriological sample submitted to department? No ; If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 368 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .025
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 203 ft. to 273 ft., From 0 ft. to 0 ft.
 From 295 ft. to 365 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 368 ft. to 20 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: **14 ABANDONED WELL**
 Direction from well? **Southwest** How many feet? **200**

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	41	BROWN CLAY			
41	47	FN-ME-CRS SAND GRAVEL			
47	203	BROWN CLAY			
203	253	GRAVEL FN-ME-CRS SAND			
253	256	BROWN CLAY			
256	272	FN-ME-CRS SAND			
272	291	BROWN CLAY			
291	304	FN-ME-CRS SAND GRAVEL			
304	324	FINE-MED SAND BRWN CLAY STRKS			
324	342	FINE-MED SAND CEMENTED STRKS			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/13/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/18/96 under the business name of HENKLE DRILLING & SUPPLY by (signature)

