

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 047 KEARNY NE 1/4 NW 1/4 SE 1/4 29 T 23 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 3 MILES NORTH AND 2 1/2 MILES WEST OF DEERFIELD

2 WATER WELL OWNER: PHIL WADDUX  
 RR#, St. Address, Box #: RT. 1, BOX 135 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: GARDEN CITY, KS 67838- Application Number: KE-006

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 391 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 90 ft. below land surface measured on mo/day/yr 03/20/93  
 Pump test data: Well water was 170 ft. after 4 hours pumping 1750 gpm  
 Estimated Yield 1750 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 391 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? No

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED  
 Blank casing diameter 16 in. to 391 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 166 ft. to 186 ft., From 210 ft. to 240 ft.  
 From 195 ft. to 205 ft., From 255 ft. to 335 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 391 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? WEST AND SOUTH How many feet? 130

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	03 SILTY CLAY			
2	19	04 SANDY CLAY			
19	142	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL			
142	152	04 SANDY CLAY 07 FINE SAND 08 MEDIUM SAND			
152	158	01 CLAY			
158	170	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
170	186	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
186	197	04 SANDY CLAY			
197	203	07 FINE SAND 08 MEDIUM SAND			
203	210	04 SANDY CLAY 20 LIMESTONE 07 FINE SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/22/93 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/24/93 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number  
COUNTY: 047 KEARNY | NE 1/4 NW 1/4 SE 1/4 | 29 | T 23 S | R 35 W

2 WATER WELL OWNER: PHIL MADDUX  
RR#, St. Address, Box #: RT. 1, BOX 135 Board of Agriculture, Division of Water Resources  
City, State, ZIP code: GARDEN CITY, KS 67838- Application Number: KE-006

SCREEN PERFORATED INTERVALS: From 363 ft. to 373 ft., From 0 ft. to 0 ft.  
From 381 ft. to 391 ft., From 0 ft. to 0 ft.

FROM	TO	LITHOLOGIC LOG
210	240	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL
240	252	01 CLAY 20 LIMESTONE 07 FINE SAND
252	260	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
260	335	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL
335	360	04 SANDY CLAY 07 FINE SAND
360	375	07 FINE SAND 08 MEDIUM SAND 01 CLAY
375	384	01 CLAY
384	388	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND
388	390	01 CLAY
390	395	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/22/93 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 03/24/93  
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce Reichert*