

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 047 KEARNY | SW 1/4 SW 1/4 SW 1/4 | 25 | T 23 S | R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM DEERFIELD; APPX 2 1/2 MILES NORTH & 1/4 MILE EAST

2 WATER WELL OWNER: MILLER MADDOX
 RR#, St. Address, Box # : RR 1 BOX 250 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : DEERFIELD, KS 67838- Application Number: 21,610

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 400ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 92 ft. below land surface measured on mo/day/yr 01/27/07
 Pump testdata: Well water was 171 ft. after 4 hours pumping 1823 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 400 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 16 in. to 400 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 20 lbs/ft. Wall thickness or gauge No. .616
 TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST
 SCREEN OR PERFORATION OPENINGS ARE: 01 CNT, SLOT

SCREEN PERFORATED INTERVALS: From 275 ft. to 395 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 400 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	20	01 CLAY			
20	89	01 CLAY 31 CALICHE 05 SAND			
89	113	07 FINE SAND 01 CLAY			
113	119	01 CLAY 05 SAND			
119	140	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
140	149	01 CLAY			
149	160	05 SAND			
160	178	07 FINE SAND 08 MEDIUM SAND 01 CLAY			
178	202	01 CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/25/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/02/07 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 047 KEARNY	SW 1/4 SW 1/4 SW 1/4	25	T 23 S	R 35 W

2 WATER WELL OWNER:	MILLER MADDUX	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RR 1 BOX 250	Application Number: 21,610
City, State, ZIP code :	DEERFIELD, KS 67838-	

FROM	TO	LITHOLOGIC LOG
202	246	01 CLAY 05 SAND
246	255	06 VERY FN SAND 07 FINE SAND
255	272	01 CLAY
272	285	05 SAND
285	296	01 CLAY
296	301	07 FINE SAND
301	306	01 CLAY
306	315	07 FINE SAND 01 CLAY
315	324	05 SAND
324	339	01 CLAY
339	360	05 SAND 11 GRAVEL 28 ROCK
360	395	05 SAND 11 GRAVEL 28 ROCK
395	397	31 CALICHE
397	410	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/25/07 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 05/02/07
 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reithmuth*