

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 047 KEARNY SE 1/4 SW 1/4 SE 1/4 12 T 23 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?

FROM DEERFIELD; APPX 5 1/2 MILES NORTH & 1 MILE EAST

2 WATER WELL OWNER: DANLER BROTHERS  
 RR#, St. Address, Box #: RT 1 BOX 440 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code: DEERFIELD, KS 67838- Application Number: 5364

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 350 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 145 ft. below land surface measured on mo/day/yr 05/01/07  
 Pump test data: Well water was 212 ft. after 4 hours pumping 1644 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 24 in. to 350 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 02 IRRIGATION  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 16 in. to 350 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 20 lbs/ft. Wall thickness or gauge No. .616  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 03 STAINLESS ST  
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 210 ft. to 350 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 20 ft. to 350 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: 14 ABAND. WELL  
 Direction from well? NORTHWEST How many feet? 112

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	120	04 SANDY CLAY 07 FINE SAND			
120	165	05 SAND 01 CLAY			
165	170	05 SAND			
170	213	05 SAND 01 CLAY			
213	234	05 SAND			
234	240	04 SANDY CLAY			
240	258	05 SAND 13 FINE GRAVEL 14 MED GRAVEL			
258	261	04 SANDY CLAY			
261	264	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/28/07 and this record is true to the best of my knowledge and belief. Kansas  
 Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 06/22/07  
 under the business name of HENKLE DRILLING & SUPPLY by (signature)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 047 KEARNY	SE 1/4 SW 1/4 SE 1/4	12	T 23 S	R 35 W

2 WATER WELL OWNER:	DANLER BROTHERS	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	RT 1 BOX 440	Application Number: 5364
City, State, ZIP code :	DEERFIELD, KS 67838-	

FROM	TO	LITHOLOGIC LOG
264	279	04 SANDY CLAY
279	332	07 FINE SAND 08 MEDIUM SAND 01 CLAY
332	350	05 SAND 28 ROCK
350	360	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION:	This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 04/28/07 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145	This Water Well Record was completed on (mo/day/yr) 06/22/07
	under the business name of HENKLE DRILLING & SUPPLY	by (signature) <i>Bruno K. Kuntz</i>