

DRILLERS TEST LOG

CUSTOMERS NAME Garden City Company DATE 2-25-77
 STREET ADDRESS Star Route #2 TEST # 13A E. LOG No
 CITY & STATE Garden City, KS DRILLER Martinez
 COUNTY Kearny QUARTER NE SECTION 32 TOWNSHIP 24 RANGE 35

LOCATION 1250' S and 600' W from the NE corner of the NE 1/4

WELL LOCATION

%	FOOTAGE			DESCRIPTION OF STRATA	Static Water Level
	From	Pay	To		Proposed Well Depth
	0		3	Top soil	
	3		40	Brown clay	
	40		54	Sand fine to med., few clay st.	
	54		80	Brown clay	
	80		91	Blue clay, sticky	
40	91	12	103	Sand fine to med. coarse, loose, used water	
	103		201	Brown clay, very few sand st.	
	201		220	Brown clay, sand st., mixed	
	220		241	Brown clay, few lime rock st.	
50	241	23	264	Sand fine to med. coarse, few small gravel, loose, used water, few white rock st., few clay st.	
	264		294	Brown clay	
60	294	7	301	Sand fine to med. coarse, small gravel, loose, used water, few white rock st., few clay st.	
	301		309	Brown clay	
60	309	16	325	Sand fine to med. coarse, few small gravel, loose, used water, few white rock st., few clay st.	
	325		327	Brown clay	
65	327	13	340	Sand fine to med. coarse, small gravel, loose, used water, few white rock st.	
75	340	25	365	Sand fine to med. coarse, small to med. gravel, loose, used water, few white rock st.	
	365		370	Yellow clay	
	370		380	Shale	
		96			
				TOTAL DEPTH OF WELL 368 FT.	
				Set up south	
				Pit on west	
					5 Quik Gel
					1 line

GARDEN CITY, KS
 Phone 276-3278

HENKLE DRILLING & SUPPLY CO., INC.
 IRRIGATION HEADQUARTERS

SUBLETTE, KS
 Phone 675-4311