

USE TYPEWRITER OR BALL POINT PEN—PRESS FIRMLY, PRINT CLEARLY.

WOLF SW

BBD

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment—Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Kearny</b>	Fraction <b>SE 1/4 NW 1/4 NW 1/4</b>	Section number <b>34</b>	Township number <b>T 23 S R 35 E/W</b>	Range number
2. Distance and direction from nearest town or city: <b>3 mi. N, 1 mi. W. of Deerfield, Kansas.</b> <small>Street address of well location in city:</small>			3. Owner of well: <b>Downing &amp; Henning Farm</b> R.R. or street: City, state, zip code: <b>Deerfield, Kansas</b>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>28</b> in. Completion date <b>10/29/76</b> Well depth <b>384</b> ft.		
		<p>1320' S &amp; 1604' W of the NE corner of NW<sub>4</sub>, Sec. 34, T23S, R35W, Kearny County, Kansas.</p>		7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Top soil		0	20	9. Casing: Material <b>stl</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>12</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>37</b> lbs./ft. Dia. <b>16</b> in. to <b>117</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <b>219</b>		
Fine sand		20	30	10. Screens: Manufacturer's name <b>Foster, Doerr</b> Type <b>milalot, lower</b> <b>16"</b> Slot/gauze <b>1/8"</b> Length <b>267'</b> Set between <b>117</b> ft. and <b>384</b> ft. ft. and <input type="checkbox"/> ft. Gravel pack? <b>yes</b> Size range of material <b>3.0mm</b>		
Tan clay		30	44	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>64</b> ft. below land surface Date <b>8/4/76</b>		
Fine to coarse sand clay streaks		44	384	12. Pumping level below land surfaces: <b>98</b> ft. after <b>1/2</b> hrs. pumping <b>1080</b> g.p.m. <b>150</b> ft. after <b>1</b> hrs. pumping <b>2500</b> g.p.m. Estimated maximum yield <b>3000</b> g.p.m.		
Black shale		384	400	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date		
				14. Well head completion: <input type="checkbox"/> Pitless adapter <input checked="" type="checkbox"/> Inches above grade		
				15. Well grouted? <b>yes</b> With: <input type="checkbox"/> Neat cement <input checked="" type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>10</b> ft.		
				16. Nearest source of possible contamination: <b>unk.</b> ft. <input type="checkbox"/> Direction <input type="checkbox"/> Type <input type="checkbox"/> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		
				17. Pump: Manufacturer's name <b>Layne &amp; Bowler</b> Model number <b>12 TH HP 120</b> Volts Length of drop pipe <b>240</b> ft. capacity <b>2000</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne &amp; Bowler Co., Inc. 102</b> Business name License No. Address <b>Garden City, Kansas</b> Signed <b>[Signature]</b> Date <b>10/26/76</b> Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley		<b>3008 (TOPO)</b>				

T 23 S R 35 E S 4 SE NW NW

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-3