

LOG OF WELL

(FOR FIELD COPIES OF DRILLERS LOGS)

STATE Kans COUNTY Keany NUMBER 6-21-62LOCATION NW 1/4 SW 1/4 SEC. 4, T. 28 R. 35DRILLER K.S.G.S. ADDRESS 4cb3SOURCE OF DATA obs E3065
(APPEND CASING RECORD AND ADDITIONAL DATA ON NOTE SHEET)250' No. 5 iron well

DRILLER'S DESCRIPTION	THICKNESS	DEPTH
surface soil	3	3
silt tan hard	12	15
clay sandy brown	17	17
caliche whitish (drilled) (medium)		
with sand str.	19	36
sand fine to coarse	6	42
caliche sandy white hard	6	48
sand fine to coarse	4	52
caliche white fine sandy	22	74
caliche brown very sandy		
& fine sand str.	12	86
clay yellowish tan sandy silty		
some caliche nodules drilled hard	12	98
caliche whitish very hard	4	102

LOG OF WELL

FIELD COPIES OF DRILLERS LOGS

STATE _____ COUNTY _____ NUMBER _____

LOCATION _____ S. 4, T. 23, R. 35

DRILLER _____ ADDRESS _____

SOURCE OF DATA
(APPEND C.A.S.ING RECORD AND ADDITIONAL DATA ON NOTE SHEET)

DRILLER'S DESCRIPTION THICKNESS DEPTH

siltstone hard with

soft silt (fine) drilled hard 8 - 110

caliche pinkish, sandy hard 8 - 118

sand, fine drilled easy; 17 - 135

shale of clay & silt

Clay 2 137

Gravel 20 157

Clay silt 2 159

Gravel 8 167

lime rock pebbles and

sand 8 175

Clay yellow sandy hard

(Laguna)? 8 183

shale Brownial Black 288 190+