

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 047 KEARMY NE 1/4 SW 1/4 SW 1/4 36 T ~~23~~ S R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1/2 MILE EAST AND 1 1/2 MILE NORTH OF DEERFIELD

2 WATER WELL OWNER: KIRK AND/OR KENT MADDUX Board of Agriculture, Division of Water Resources
 RR#, St. Address, Box #: P.O. BOX 136 Application Number: 1847
 City, State, ZIP code: DEERFIELD, KS 67838-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 393 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 104 ft. below land surface measured on mo/day/yr 07/14/94
 Pump test data: Well water was 280 ft. after 24 hours pumping 1115 gpm
 Estimated Yield 1150 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 393 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 393 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 190 ft. to 390 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 393 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? NORTHEAST How many feet? 275

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	02 SILT			
3	23	04 SANDY CLAY 05 SAND			
23	26	07 FINE SAND			
26	65	04 SANDY CLAY 07 FINE SAND			
65	72	04 SANDY CLAY 31 CALICHE			
72	80	01 CLAY			
80	90	07 FINE SAND			
90	100	01 CLAY			
100	120	08 MEDIUM SAND 13 FINE GRAVEL 04 SANDY CLAY			
120	150	17 SAND & GRAVL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/13/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/18/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

