

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction : Section Number : Township Number : Range Number  
 COUNTY: 047 KEARNY : SW 1/4 NE 1/4 NE 1/4 : 15 : T 23 S : R 35 W

Distance and direction from nearest town or city street address of well if located within city?  
 APPROX. 5 MILES NORTH OF DEERFIELD

2 WATER WELL OWNER: GRAHM FARMS  
 RR#, St. Address, Box #: BOX 1004 Board of Agriculture, Division of Water Resources  
 City, State, ZIP code : LAKIN, KS 67860- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 335 ELEVATION: 0  
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.  
 WELL'S STATIC WATER LEVEL 130 ft. below land surface measured on mo/day/yr 11/30/94  
 Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm  
 Bore Hole Diameter 9.875 in. to 335 ft., and in. to 0 ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 335 ft., Dia in. to 0 ft., Dia in. to 0 ft.  
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 275 ft. to 335 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 335 ft., From 0 ft. to 0 ft.  
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.  
 What is the nearest source of possible contamination: NONE OBSERVED  
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	16	03 SILTY CLAY			
16	80	01 CLAY 04 SANDY CLAY			
80	97	04 SANDY CLAY 07 FINE SAND			
97	192	01 CLAY			
192	197	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
197	200	01 CLAY			
200	236	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
236	239	01 CLAY			
239	330	07 FINE SAND 09 COARSE SAND 04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/30/94 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/13/94 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number  
COUNTY: 047 KEARNY | SW 1/4 NE 1/4 NE 1/4 | 15 | T 23 S | R 35 W

2 WATER WELL OWNER: GRAHM FARMS  
RR#, St. Address, Box #: BOX 1004 Board of Agriculture, Division of Water Resources  
City, State, ZIP code: LAKIN, KS 67860- Application Number:

FROM	TO	LITHOLOGIC LOG
330	335	07 FINE SAND 09 COARSE SAND 11 GRAVEL
335	341	01 CLAY 20 LIMESTONE 19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/30/94 and this record is true to the best of my knowledge and belief. Kansas  
Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 12/13/94  
under the business name of HENKLE DRILLING & SUPPLY by (signature) Bruce J. Richmond