

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 047 KEARNY SW 1/4 SW 1/4 SE 1/4 3 T 23 S R 35 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1/2 MILES NORTH AND 1/2 MILE WEST OF DEERFIELD

2 WATER WELL OWNER: GERALD D. MILLER
 RRF, St. Address, Box #: 2201 CENTER Board of Agriculture, Division of Water Resources
 City, State, ZIP code: GARDEN CITY, KS 67846- Application Number: 21,238 28,298

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 270 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 150 ft. below land surface measured on mo/day/yr 01/12/95
 Pump test data: Well water was 216 ft. after 2 hours pumping 840 gpm
 Estimated Yield 850 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 24 in. to 270 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 02 IRRIGATION
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 01 STEEL CASING JOINTS: WELDED
 Blank casing diameter 16 in. to 270 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 42 lbs/ft. Wall thickness or gauge No. .250
 TYPE OF SCREEN OR PERFORATION MATERIAL: 01 STEEL
 SCREEN OR PERFORATION OPENINGS ARE: 01 CONT. SLOT

SCREEN PERFORATED INTERVALS: From 235 ft. to 265 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 20 ft. to 270 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 0 ft. to 20 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: 14 ABAND. WELL
 Direction from well? WEST How many feet? 190

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1	02 SILT			
1	10	03 SILTY CLAY			
10	43	01 CLAY			
43	83	04 SANDY CLAY			
83	94	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
94	125	04 SANDY CLAY 05 SAND			
125	150	07 FINE SAND 09 COARSE SAND 11 GRAVEL			
150	168	04 SANDY CLAY 07 FINE SAND			
168	183	07 FINE SAND 08 MEDIUM SAND 09 COARSE SAND			
183	186	04 SANDY CLAY			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/10/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/16/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
COUNTY: 047 KEARNY	SW 1/4 SW 1/4 SE 1/4	3	T 23 S	R 35 W

2 WATER WELL OWNER:	GERALD D. MILLER	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	2201 CENTER	Application Number: 21,236 28,296
City, State, ZIP code :	GARDEN CITY, KS 67846-	

FROM	TO	LITHOLOGIC LOG
186	191	04 SANDY CLAY 20 LIMESTONE
191	207	20 LIMESTONE 07 FINE SAND 04 SANDY CLAY
207	222	01 CLAY 04 SANDY CLAY 20 LIMESTONE
222	235	04 SANDY CLAY 07 FINE SAND
235	256	07 FINE SAND 09 COARSE SAND 14 MED GRAVEL
256	259	20 LIMESTONE 04 SANDY CLAY 31 CALICHE
259	261	20 LIMESTONE
261	280	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 01/10/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 01/16/95 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruno Reichmuth*