

DRILLERS TEST LOG

CUSTOMER'S NAME: Nelly Thomas DATE: 6-27-89
 STREET ADDRESS: RR 108 Russell Rd, TEST # 1 E. LOG Yes
 CITY & STATE: Lakin, KS 67860 DRILLER Norman
 COUNTY Kearney QUARTER SE SECTION 14 TOWNSHIP 23 RANGE 36

LOCATION 15' East of Old well

%	FOOTAGE			DESCRIPTION OF STRATA	STATIC WATER LEVEL:
	From	Pay	TO		Proposed Well Depth:
	0		2	Top soil	
	2		14	Brown, sandy clay	
	14		31	Sand, fine to medium coarse, small gravel, 4 small clay streaks	
	31		43	Brown clay	
	43		62	Sand, fine to medium coarse	
	62		95	Brown & gray clay	
60	95	21	129	Sand, fine to medium coarse, small gravel, some white rock	
50	129	11	140	Fine to medium coarse, silty sand,	
	140		146	Soap stone & limestone ledges	
	146		162	Black shale & hard gray shale ledges	
		32			
				TD 145'	
				5" PVC	
				Perf Plain	
	145		115	30'	
	115		0		115'
				TOTAL 30'	115'
				1 - 50# bag Hi-Tek	
				6 - 50# bags Hole Plug	
				1 - set 4 3/4 Drag Blades	
				1/4 of 9 7/8" Bit Life	
				2 - 5" PVC Caps	

GARDEN CITY, KS 67846
 3795 West Jones Ave.

HENKLE DRILLING & SUPPLY CO., INC.

316-277-2389

IRRIGATION HEADQUARTERS

TEST HOLES * * * * * IRRIGATION & INDUSTRIAL WELLS * * * * * STOCK WELLS