

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 047 KEARNY SW 1/4 SW 1/4 SW 1/4 01 T 23 S R 37 W

Distance and direction from nearest town or city street address of well if located within city?
 FROM LAKIN; APPX 3 1/2 MILES WEST & 9 MILES NORTH

2 WATER WELL OWNER: BILLY MOORE
 RR#, St. Address, Box # : RR 1 BOX 27 Board of Agriculture, Division of Water Resources
 City, State, ZIP code : LAKIN, KS 67860-9802 Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

NW	NE	SE	SW
X			

4 DEPTH OF COMPLETED WELL 220 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 110 ft. below land surface measured on mo/day/yr 07/10/04
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 10 in. to 220 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 220 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 3 lbs/ft. Wall thickness or gauge No. .265
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 180 ft. to 226 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 220 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	02 SILT			
2	9	04 SANDY CLAY			
9	68	05 SAND 13 FINE GRAVEL			
68	93	04 SANDY CLAY			
93	100	07 FINE SAND 08 MEDIUM SAND			
100	103	04 SANDY CLAY			
103	108	07 FINE SAND 08 MEDIUM SAND			
108	124	04 SANDY CLAY			
124	140	07 FINE SAND 08 MEDIUM SAND			
140	152	05 SAND			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/09/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04 under the business name of HENKLE DRILLING & SUPPLY by (signature) -

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 047 KEARNY SW 1/4 SW 1/4 SW 1/4 01 T 23 S R 37 W

2 WATER WELL OWNER: BILLY MOORE
RR#, St. Address, Box # : RR 1 BOX 27 Board of Agriculture, Division of Water Resources
City, State, ZIP code : LAKIN, KS 67860-9802 Application Number:

FROM	TO	LITHOLOGIC LOG
152	165	04 SANDY CLAY
165	177	07 FINE SAND 08 MEDIUM SAND
177	212	05 SAND 28 ROCK
212	216	05 SAND
216	220	31 CALICHE
220	225	19 SHALE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 07/09/04 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 08/31/04
under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Richman*