

WATER WELL RECORD Form #WC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
 COUNTY: 038 HAMILTON | NE 1/4 NE 1/4 NW 1/4 | 34 | T 23 S | R 41 W

Distance and direction from nearest town or city street address of well if located within city?
 APPROX. 1 1/2 MILES NORTH & 2 1/2 MILES WEST OF SYRACUSE.

2 WATER WELL OWNER: COWNTOWN FEEDERS INC.
 RR#, St. Address, Box #: BOX 1088 Board of Agriculture, Division of Water Resources
 City, State, ZIP code: SYRACUSE, KS 67878- Application Number: 41,113

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: | 4 DEPTH OF COMPLETED WELL 401 ELEVATION: 0
 Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.
 WELL'S STATIC WATER LEVEL 258 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was 0 ft. after 0 hours pumping 0 gpm
 Estimated Yield 70 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm
 Bore Hole Diameter 17.5 in. to 401 ft., and in. to 0 ft.
 WELL WATER TO BE USED AS: 03 FEEDLOT
 Was a chemical/bacteriological sample submitted to department? No;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 8 in. to 401 ft., Dia in. to 0 ft., Dia in. to 0 ft.
 Casing height above land surface 12 in., weight 7 lbs/ft. Wall thickness or gauge No. .410
 TYPE OF SCREEEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 03 MILL SLOT

SCREEN PERFORATED INTERVALS: From 321 ft. to 401 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 401 ft., From 0 ft. to 0 ft.
 From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 5 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
 What is the nearest source of possible contamination: NONE OBSERVED
 Direction from well? How many feet? 0

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	19	01 CLAY			
19	25	01 CLAY 09 COARSE SAND			
25	39	01 CLAY			
39	70	19 SHALE 20 LIMESTONE			
70	100	19 SHALE 20 LIMESTONE			
100	110	19 SHALE 20 LIMESTONE			
110	161	19 SHALE			
161	171	19 SHALE 20 LIMESTONE			
171	180	19 SHALE			
180	188	19 SHALE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 06/29/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/05/95 under the business name of HENKLE DRILLING & SUPPLY by (signature)

(Continued)

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: | Fraction | Section Number | Township Number | Range Number
COUNTY: 038 HAMILTON | NE 1/4 NE 1/4 NW 1/4 | 34 | T 23 S | R 41 W

2 WATER WELL OWNER: COWTOWN FEEDERS INC.
RR#, St. Address, Box # : BOX 1088 Board of Agriculture, Division of Water Resources
City, State, ZIP code : SYRACUSE, KS 67878- Application Number: 41,113

FROM	TO	LITHOLOGIC LOG
188	220	19 SHALE
220	224	19 SHALE 20 LIMESTONE
224	250	19 SHALE
250	265	19 SHALE 20 LIMESTONE
265	275	23 SANDSTONE 20 LIMESTONE
275	290	20 LIMESTONE 19 SHALE
290	324	20 LIMESTONE
324	336	20 LIMESTONE 23 SANDSTONE
336	341	23 SANDSTONE
341	356	31 CALICHE
356	375	31 CALICHE 23 SANDSTONE
375	401	23 SANDSTONE 31 CALICHE
401	430	19 SHALE 34 PYRITE

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed under my jurisdiction and was completed on (mo/day/year) 06/29/95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 145 This Water Well Record was completed on (mo/day/yr) 07/05/95 under the business name of HENKLE DRILLING & SUPPLY by (signature) *Bruce J. Reichmuth*