

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

2391W33NE4E  
T R EW sec 1/4 1/4 1/4 No.

WATER WELL RECORD  
KSA 82a-1201-1215


Kansas State Dept. Of Health  
(Water Well Contractors)  
Forbes-Bldg. 740  
Topeka, Kansas 66620

1 Location of well: County Hamilton Township name Syracuse Fraction NE<sup>1</sup>/<sub>4</sub> NE<sup>1</sup>/<sub>4</sub> NE<sup>1</sup>/<sub>4</sub> Section number 33 Town number 235 Range number #1 W

Distance and direction from nearest town or city:  
3 mile West, 1 mile North of Syracuse, Kans.  
Street address of well location if in city:

3 Owner of well: Syracuse Country Club, Inc.  
Address: Syracuse, Kansas 67878

Locate with "X" in section below:



Sketch map: N



4 Well depth: 435 ft. Date of completion 5/15 1975  
Well diameter 9 in.

5  Cable tool  Rotary  Driven  Dug  
 Hollow rod  Jetted  Bored  Reverse rotary

6 Use:  Domestic  Public supply  Industry  
 Irrigation  Air conditioning  Commercial  
 Test well

7 Casing: Material Steel Height: above/below  
Threaded  Welded  Surface 30 in.  
Dig. \_\_\_\_\_ Weight \_\_\_\_\_ lbs./ft.  
6 3/4 in. to 405 ft. depth Drive shoe?  Yes  No  
\_\_\_\_\_ in. to \_\_\_\_\_ ft. depth

2

Type and color of material	From	To
<u>Top soil</u>	<u>0</u>	<u>5'</u>
<u>Clay</u>	<u>5</u>	<u>30</u>
<u>Shale</u>	<u>30</u>	<u>370</u>
<u>Dakota sand</u>	<u>370'</u>	<u>435'</u>

8 Screen:  
Manufacturer Lake Wood Pipe of Texas  
Type Steel Dia. 6 3/4"  
Slot/gauze Teach-ty Length 30'  
Set between 375 ft. and 405 ft.  
Fittings:  
Gravel pack  Yes  No Size range of material 3/8"

9 Static water level:  
140 ft. below land surface Date 6-13-75

10 Pumping level below land surfaces:  
300 ft. after 9 hrs. pumping 55 g.p.m.  
\_\_\_\_\_ ft. after \_\_\_\_\_ hrs. pumping \_\_\_\_\_ g.p.m.  
Estimated maximum yield 55 g.p.m.

11 Water sample submitted:  
 Yes  No Date \_\_\_\_\_

12 Well head completion:  
 Pitless adapter  Inches above grade

13 Well grouted?  Yes  No  
 Neat cement  Bentonite  \_\_\_\_\_  
Depth: From 0 ft. to 10 ft.

14 Nearest source of possible contamination:  
ft. 250 Direction N-NW Type Lake  
Well disinfected upon completion?  Yes  No

15 Pump:  Not installed  
Manufacturer's name Hydraulic Products, Inc  
Model number 50616 HP 20 Volts 440  
Length of drop pipe 320 ft. capacity 100 g.p.m.  
Type:  
 Submersible  Turbine  
 Jet  Reciprocating  
 Centrifugal  Other

16 Remarks: elevation 3185  
This well is not used for drinking - is only used for watering the greens on the golf course  
Well is open hole from 405' to 435'

Topography:  
 Hill  
 Slope  
 Upland  
 Valley

17 Water well contractor's certification:  
This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.  
Dreiling, Inc. 210 License No.  
Business name  
Address Box 457 Holly, Colo. 81047  
Signed D. J. Dreiling Date \_\_\_\_\_  
Authorized representative