

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

topeka

1. Location of well:	County RENO	Fraction SE 1/4 NE 1/4 SW 1/4	Section number 34 North	Township number T 23 S	Range number R 5 E																								
2. Distance and direction from nearest town or city: Street address of well location, if in city: 1 EAST OF HUTCH ON 30th ST. Lot # 8 blk. #1			3. Owner of well: R.R. or street: Lynn Schwartz Kopf 2808 N MONROE Hutchinson, KANSAS City, state, zip code:																										
4. Locate with "X" in section below: N W E S 1 Mile 1 Mile			6. Bore hole dia. 10 in. Completion date 8-26-77 X Well depth 108 ft.																										
			7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary																										
			8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																										
5. Type and color of material			9. Casing: Material plastic Height: 12 in. Threaded ☐ Welded ☒ Surface ☐ RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. 5 in. to 108 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 2256																										
<table border="1"> <thead> <tr> <th></th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr> <td>SAND "dune fill"</td> <td>0</td> <td>5</td> </tr> <tr> <td>SANDY loam</td> <td>5</td> <td>10</td> </tr> <tr> <td>dune sand</td> <td>10</td> <td>27</td> </tr> <tr> <td>grey clay & fine sand</td> <td>27</td> <td>61</td> </tr> <tr> <td>fine sand w/ grey clay layered</td> <td>61</td> <td>85</td> </tr> <tr> <td>fine sand brown</td> <td>85</td> <td>105</td> </tr> <tr> <td>grey clay</td> <td>105</td> <td>108</td> </tr> </tbody> </table>				From	To	SAND "dune fill"	0	5	SANDY loam	5	10	dune sand	10	27	grey clay & fine sand	27	61	fine sand w/ grey clay layered	61	85	fine sand brown	85	105	grey clay	105	108	10. Screen: Manufacturer's name Western Plastics Type PVC Dia. 5" Slot/gauze .020 Length 20' Set between 85 ft. and 105 ft. Gravel pack? ☒ Size range of material 18/44		
				From	To																								
			SAND "dune fill"	0	5																								
			SANDY loam	5	10																								
			dune sand	10	27																								
			grey clay & fine sand	27	61																								
			fine sand w/ grey clay layered	61	85																								
			fine sand brown	85	105																								
			grey clay	105	108																								
			11. Static water level: 27 ft. below land surface Date 8-26-77																										
12. Pumping level below land surfaces: 38 ft. after 3 hrs. pumping 18 g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 100 g.p.m.																													
13. Water sample submitted: ☒ Yes ☐ No Date ☐																													
14. Well head completion: ☒ Pitless adapter ☐ Inches above grade																													
15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.																													
16. Nearest source of possible contamination: ft. 95' Direction EAST Type SEWER Well disinfected upon completion? ☒ Yes ☐ No																													
17. Pump: Not installed Manufacturer's name Dempster Model number DFH-75-5-HP Volts 230 Length of drop pipe 75 ft. capacity 18 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																													
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. PAUL'S INC #175 Business name Hesston, KNS License No. Address Paul B. Bunt Date 8/30/77 Signed Paul B. Bunt Authorized representative																										