

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Reno		NW ¼ NE ¼ NW ¼	2	T 23 S	R 5 EW
Distance and direction from nearest town or city street address of well if located within city? 2 mi E of Hutchinson - 2801 Links Land Dr					
2 WATER WELL OWNER:					
RR#, St. Address, Box # :		Board of Agriculture, Division of Water Resources			
City, State, ZIP Code :		Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL.			
		Depth(s) Groundwater Encountered 1.....ft. 2.....ft. 3.....ft. ELEVATION: ft.			
		WELL'S STATIC WATER LEVEL ... 27 ... ft. below land surface measured on mo/day/yr ... 4-8-94 ...			
		Pump test data: Well water was ... 40 ... ft. after ... ½ ... hours pumping ... 25 ... gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter ... 9 ... in. to ... 1.14 ... ft., and in. to ft.			
		WELL WATER TO BE USED AS: ☒ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Injection well ☐ Irrigation ☐ Industrial ☐ Lawn and garden only ☐ Monitoring well ☐ Other (Specify below)			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No.... X ...; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes X No			
5 TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)		CASING JOINTS: Glued X Clamped	
☒ PVC		4 ABS		Welded	
		7 Fiberglass		Threaded	
Blank casing diameter 5 ... in. to 7.3 ... ft., Dia in. to ft., Dia in. to ft.					
Casing height above land surface 12 ... in., weight 2.27 ... lbs./ft. Wall thickness or gauge No. 160 ...					
TYPE OF SCREEN OR PERFORATION MATERIAL:					
1 Steel		3 Stainless steel		5 Asbestos-cement	
2 Brass		4 Galvanized steel		6 Concrete tile	
		5 Fiberglass		8 RMP (SR)	
		6 Concrete tile		9 ABS	
				10 Asbestos-cement	
				11 Other (specify)	
				12 None used (open hole)	
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot		3 Mill slot		5 Gauzed wrapped	
2 Louvered shutter		4 Key punched		6 Wire wrapped	
				7 Torch cut	
				10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From 7.3 ... ft. to 11.3 ... ft., From ft. to ft.					
GRAVEL PACK INTERVALS: From 40 ... ft. to 50 ... ft., From ft. to ft.					
From 55 ... ft. to 114 ... ft., From ft. to ft.					
6 GROUT MATERIAL:					
1 Neat cement		2 Cement grout		3 Bentonite	
Grout Intervals: From 3 ... ft. to 23 ... ft., From 50 ... ft. to 55 ... ft., From ft. to ft.					
What is the nearest source of possible contamination:					
☒ Septic tank		4 Lateral lines		7 Pit privy	
2 Sewer lines		5 Cess pool		8 Sewage lagoon	
3 Watertight sewer lines		6 Seepage pit		9 Feedyard	
				10 Livestock pens	
				11 Fuel storage	
				12 Fertilizer storage	
				13 Insecticide storage	
				14 Abandoned water well	
				15 Oil well/Gas well	
				16 Other (specify below)	
Direction from well? E					
How many feet? 110					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	19	F Sand			
19	22	Sandy Br Clay			
22	34	F Sand			
34	69	Sandy Br & Gr Clay			
69	114	F sand - sm layers clay			
114	115	Br clay			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4-10-94 ... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 447 ... This Water Well Record was completed on (mo/day/yr) 4-10-94 ... under the business name of Miller Drilling by (signature) [Signature]					

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.