



USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Reno</u>	Fraction <u>SE 1/4 SE 1/4 NE 1/4</u>	Section number <u>2</u>	Township number <u>T 23</u>	Range number <u>S R 5</u>	<u>EW</u>
2. Distance and direction from nearest town or city: <u>3 E 1/2 S of Hwy 61 on 30th</u> Street address of well location if in city: <u>Hutchinson</u>				3. Owner of well: <u>Ray Showalter</u> R.R. or street: <u>RR 5</u> City, state, zip code: <u>Hutchinson, Kan 67501</u>			
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>12</u> in. Completion date <u>3-1-77</u> Well depth <u>67</u> ft.			
				7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary			
5. Type and color of material		From		To		8. Use: <input checked="" type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input checked="" type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
fine sand		0		2		9. Casing: Material <u>Plas</u> Height: <u>Above</u> or below Threaded <input type="checkbox"/> Welded <u>6</u> Surface <u>12</u> in. RMP <input checked="" type="checkbox"/> PVC <input type="checkbox"/> Weight <u> </u> lbs./ft. Dia. <u>6</u> in. to <u>67</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>175</u>	
dk grey clay		2		9		10. Screen: Manufacturer's name <u>J & L</u> Type <u>RMP</u> Dia. <u>6"</u> Slot/gauze <u>1/8 hole</u> Length <u>25'</u> Set between <u>42</u> ft. and <u>67</u> ft. Gravel pack? <u>yes</u> Size range of material <u>1/8-1/2"</u>	
fine sand		9		14		11. Static water level: <u>26</u> ft. below land surface Date <u>3-1-77</u> mo./day/yr.	
grey clay		14		19		12. Pumping level below land surfaces: <u>35</u> ft. after <u>1</u> hrs. pumping <u>15</u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u>20</u> g.p.m.	
fine sand		19		27		13. Water sample submitted: <u> </u> mo./day/yr. <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <u> </u>	
sandy brown clay		27		36		14. Well head completion: <input checked="" type="checkbox"/> Pitless adapter <u>12</u> inches above grade	
fine sand		36		55		15. Well grouted? <u>yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>3</u> ft. to <u>13</u> ft.	
sandy brown clay		55		60		16. Nearest source of possible contamination: ft. <u>60</u> Direction <u>South</u> Type <u>Septic</u> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
fine sand		60		67		17. Pump: <u> </u> Not installed Manufacturer's name <u>Aer motor</u> Model number <u>SP 12</u> HP <u>1/2</u> Volts <u>230</u> Length of drop pipe <u>40</u> ft. capacity <u>15</u> g.p.m. Type: <input checked="" type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)							
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Price Water Well 193</u> Business name <u>RR 3 Hutchinson</u> License No. <u> </u> Address <u>John Davenport</u> Date <u>8-20-77</u> Signed <u> </u> Authorized representative			
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley							

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5