

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Reno		SE ¼ NW ¼ NW ¼	28	T 23 S	R 6 E W
Distance and direction from nearest town or city street address of well if located within city? 1910 S. Broadacres Road, Hutchinson					
2 WATER WELL OWNER: Koch Underground Storage					
RR#, St. Address, Box # : 1910 S. Broadacres Road					
City, State, ZIP Code : Hutchinson, KS 67501					
Board of Agriculture, Division of Water Resources Application Number:					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 198 ft. ELEVATION: 0			
		Depth(s) Groundwater Encountered 1. 23 ft. 2. 23 ft. 3. 23 ft.			
		WELL'S STATIC WATER LEVEL: 46.93 ft. below land surface measured on mo/day/yr 6/29/2005			
		Pump test data: Well water was NA ft. after NA hours pumping NA gpm			
		Est. Yield NA gpm: Well water was NA ft. after NA hours pumping NA gpm			
		Bore Hole Diameter 7 in. to 200 ft. and NA in. to NA ft.			
		WELL WATER TO BE USED AS:			
		1 Domestic 3 Feedlot 6 Oil field water supply 8 Air conditioning 11 Injection well			
		2 Irrigation 4 Industrial 7 Lawn and garden only 9 Dewatering 12 Other (Specify below)			
		Was a chemical/bacteriological sample submitted to Department? Yes ☒ No ☒ If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes ☒ No ☒			
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued ☐ Clamped ☐					
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded ☐					
Blank casing diameter 2 in. to 163 ft. Dia 163 in. to NA ft. Dia NA in. to NA ft.					
Casing height above land surface 30 in., weight NA lbs./ft. Wall thickness or gauge No. Sch. 40					
TYPE OF SCREEN OR PERFORATION MATERIAL					
1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement					
2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) ☐					
SCREEN OR PERFORATION OPENINGS ARE:					
1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)					
2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes					
7 Torch cut 10 Other (specify) ☐					
SCREEN-PERFORATED INTERVALS: From 163 ft. to 198 ft. From NA ft. to NA ft.					
GRAVEL PACK INTERVALS: From 160 ft. to 198 ft. From NA ft. to NA ft.					
6 GROUT MATERIAL:					
1 Neat cement 2 Cement grout 3 Bentonite 4 Other ☐					
Grout Intervals: From 0 ft. to 156 ft. From 156 ft. to 160 ft. From NA ft. to NA ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)					
13 Insecticide storage					
Direction from well? 0 How many feet?					
FROM TO LITHOLOGIC LOG FROM TO PLUGGING INTERVALS					
0 2 Topsoil, sandy, Lt. Brown					
2 30 Clay, silty, Lt. Brown					
30 40 Clay, sandy (f), well sorted, Lt. Brown					
40 50 Sand (f-m), fair to good sorting, some clay, Lt.					
50 70 Sand (f-c), tr. gravel, some caliche, poor sortin					
70 90 Sand (f-m), fair sorting,					
90 100 Sand (f-c), poor sorting,					
100 140 Sand (f-m), fair sorting,					
140 174 Sand (f), well sorted,					
174 180 Shale, firm to hard, some sand cavings, Green					
180 200 Shale, very firm, some sand cavings, Red to G					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6/21/2005 and this record is true to the best of my knowledge and belief.					
Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 6-29-05					
under the business name of GeoCore, Inc. by (signature) <i>[Signature]</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.					

 $\frac{1}{2}$