

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Reno		SE 1/4 SW 1/4 NE 1/4	29	T 23 S	R 6 E W
Distance and direction from nearest town or city street address of well if located within city? 2610 S. Mohawk Rd., Hutchinson					
2 WATER WELL OWNER: Ferrellgas					
RR#, St. Address, Box # : 2610 S. Mohawk Road			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : So. Hutchinson, KS 67505			Application Number:		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 217 ft. ELEVATION: 1582.51			
		Depth(s) Groundwater Encountered 1 _____ ft. 2 _____ ft. 3 _____ ft.			
		WELL'S STATIC WATER LEVEL 43.44 ft. below land surface measured on mo/day/yr 8/3/2005			
		Pump test data: Well water was NA ft. after _____ hours pumping _____ gpm			
		Est. Yield NA gpm. Well water was _____ ft. after _____ hours pumping _____ gpm			
		Bore Hole Diameter 6.75 in. to 218 ft. and _____ in. to _____ ft.			
WELL WATER TO BE USED AS:		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒		If yes, mo/day/yr sample was submitted			
Water Well Disinfected? Yes _____ No ☒					
5 TYPE OF BLANK CASING USED:					
1 Steel 3 RMP (SR)		5 Wrought iron 8 Concrete tile		CASING JOINTS: Glued _____ Clamped _____	
2 PVC 4 ABS		6 Asbestos-Cement 9 Other (specify below)		Welded _____	
Blank casing diameter 2 in. to 182 ft. Dia _____ in. to _____ ft. Dia _____ in. to _____ ft.		7 Fiberglass		Threaded ☒	
Casing height above land surface 30 in. weight _____ lbs./ft. Wall thickness or gauge No. Sch. 40					
TYPE OF SCREEN OR PERFORATION MATERIAL					
1 Steel 3 Stainless steel 5 Fiberglass		7 PVC		10 Asbestos-cement	
2 Brass 4 Galvanized steel 6 Concrete tile		8 RMP (SR)		11 Other (specify) _____	
SCREEN OR PERFORATION OPENINGS ARE:		9 ABS		12 None used (open hole)	
1 Continuous slot 3 Mill slot		5 Gauzed wrapped		8 Saw cut 11 None (open hole)	
2 Louvered shutter 4 Key punched		6 Wire wrapped		9 Drilled holes	
SCREEN-PERFORATED INTERVALS: From 182 ft. to 217 ft. From _____ ft. to _____ ft.		7 Torch cut		10 Other (specify) _____	
GRAVEL PACK INTERVALS: From 177 ft. to 218 ft. From _____ ft. to _____ ft.					
6 GROUT MATERIAL:					
1 Neat cement 2 Cement grout 3 Bentonite 4 Other _____					
Grout Intervals: From 0 ft. to 173 ft. From 173 ft. to 177 ft. From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy		10 Livestock pens 14 Abandoned water well			
2 Sewer lines 5 Cess pool 8 Sewage lagoon		11 Fuel storage 15 Oil well/Gas well			
3 Watertight sewer lines 6 Seepage pit 9 Feedyard		16 Other (specify below) Brine pond			
Direction from well?		How many feet?			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	5	Clay, soft, silty, Brown	140	150	Sand (f-c), clayey, lot of rock frags, Tan
5	10	Clay, silty, firm, Reddish Brown	150	160	Sand (f-c),
10	20	Clay, silty, soft, Brown	160	180	Sand (f-m),
20	30	As above w/white limy gravel @ 26'	180	193.5	Sand (f-c), green shale frags.
30	36	Clay, silty, soft, tr. fine sand, Brown	193.5	200	Shale, sandy, Red
36	40	Clay, firm, Brown	200	218	Shale, sandy, Red w/tr. Green
40	42	Clay, sandy, Brown			
42	47	Sand,			
47	49.5	Clay, Brown			
49.5	60	Sand (f-m), thin clay lenses.			
60	70	Sand (f-vc), thin brown clay lenses.			
70	90	Sand (f-c),			
90	100	Sand (f-c), clayey.			MW15D, Abovegrade
100	110	Sand (f-m), clayey.			Project Name: GeoStat - Ferrellgas
110	140	Sand (f-c), tr. clay.			GeoCore # 1160, #
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7/22/2005 and this record is true to the best of my knowledge and belief.					
Kansas Water Well Contractor's License No. 527		This Water Well Record was completed on (mo/day/yr) 8/12/05			
under the business name of GeoCore, Inc.		by (signature) <i>[Signature]</i>			

OFFICE USE ONLY

T

R

EW

SEC

K

K

S