

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Reno	SW ¼ SW ¼ NE ¼	29	T 23 S	R 6 E/W

Distance and direction from nearest town or city street address of well if located within city?

2610 S. Mohawk Rd., So. Hutchinson

2 WATER WELL OWNER: Ferrellgas	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # : 2610 S. Mohawk Road	Application Number:
City, State, ZIP Code : So. Hutchinson, KS 67505	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 221 ft. ELEVATION: 1582.38
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL: 41.79 ft. below land surface measured on mo/day/yr: 8/3/2005
	Pump test data: Well water was NA ft. after hours pumping gpm
	Est. Yield NA gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter: 6.75 in. to 221 ft. and in. to ft.
WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well	
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)	
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes.....No ☒ ; If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes No ☒	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped
1 Steel	3 RMP (SR)	9 Other (specify below)	Welded
2 PVC	4 ABS	7 Fiberglass	Threaded. ☒
Blank casing diameter: 2 in. to 186 ft. Dia. in. to ft. Dia. in. to ft.			
Casing height above land surface: 29.04 in., weight lbs./ft. Wall thickness or gauge No. Sch. 40			
TYPE OF SCREEN OR PERFORATION MATERIAL			
1 Steel	3 Stainless steel	5 Fiberglass	7 PVC
2 Brass	4 Galvanized steel	6 Concrete tile	8 RMP (SR)
			9 ABS
			10 Asbestos-cement
			11 Other (specify)
			12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	8 Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
		7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS: From 186 ft. to 221 ft. From ft. to ft.			
GRAVEL PACK INTERVALS: From 180 ft. to 221 ft. From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From 0 ft. to 173 ft. From 173 ft. to 180 ft. From ft. to ft.				
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
			13 Insecticide storage	Brine pond
Direction from well? How many feet?				

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Topsoil, roots, Brown to Black			
2	36	Clay, Brown			
36	60	Sand (f-c), quartz and pink feldspar, angular t			
60	70	Sand (f), fair sorting, Tan			
70	80	Sand (f-m), quartz and pink feldspar, Tan			
80	90	Gravel and Sand (f-c) some sm. gravel, Tan			
90	119	Gravel and Sand (f-c), sm. gravel, angular, Ta			
119	123	Clay, soft, Tan			
123	135	Sand (f-m), fair sorting, Tan			
135	155	Sand (f-c), poor sorting, Tan			
155	196	Sand (f), fair sorting, Tan			
196	205	Shale, Green to Gray to Dark Red with depth			
205	221	Shale, some sand and gray shale cavings, Mar			
					MW20DR, Abovegrade
					Project Name: GeoStat - Ferrellgas
					GeoCore # 1160, #

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 7/22/2005 and this record is true to the best of my knowledge and belief.
Kansas Water Well Contractor's License No. 527 This Water Well Record was completed on (mo/day/yr) 8/12/05 under the business name of GeoCore, Inc. by (signature) <i>Don Holt</i>