

1 LOCATION OF WATER WELL:		Fraction	Section Number		Township Number	Range Number
County: Reno		SW 1/4 NW 1/4 SW 1/4	16		T 23 S	R 6 E/W
Distance and direction from nearest town or city street address of well if located within city?						
Approx. 2 mi. west of Hutchinson, KS						
2 WATER WELL OWNER:		Reno Co. Landfill				
RR#, St. Address, Box # :		206 W. First				
City, State, ZIP Code :		Hutchinson, KS 67501				
		Board of Agriculture, Division of Water Resources Application Number: n/a				
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 58.5 ft. ELEVATION: unknown				
		Depth(s) Groundwater Encountered 1. 19'6" ft. 2. ft. 3. ft.				
		WELL'S STATIC WATER LEVEL 19'6" ft. below land surface measured on mo/day/yr 1/6/86				
		Pump test data: Well water was not ck'd after hours pumping gpm				
		Est. Yield n/a gpm: Well water was ft. after hours pumping gpm				
		Bore Hole Diameter 8 in. to 56 ft., and in. to ft.				
		WELL WATER TO BE USED AS:				
		5 Public water supply 8 Air conditioning 11 Injection well				
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)				
		2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well MONITOR				
		Was a chemical/bacteriological sample submitted to Department? Yes No X; If yes, mo/day/yr sample was submitted				
		Water Well Disinfected? Yes No X				
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued XX Clamped				
1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded						
2 PVC 4 ABS 7 Fiberglass Threaded						
Blank casing diameter 4 in. to 30 ft., Dia in. to ft., Dia in. to ft.						
Casing height above land surface 30 in., weight 2.001 lbs./ft. Wall thickness or gauge No. 237						
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement				
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)						
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)						
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)				
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes						
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)						
SCREEN-PERFORATED INTERVALS: From 30 ft. to 56 ft., From ft. to ft.						
GRAVEL PACK INTERVALS: From 12 ft. to 56 ft., From ft. to ft.						
6 GROUT MATERIAL: a) 1 Neat cement 2 Cement grout b) 3 Bentonite 4 Other						
Grout Intervals: From 0 ft. to 10 ft., From 10 ft. to 12 ft., From ft. to ft.						
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well				
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well						
2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below)						
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage LANDFILL						
Direction from well?		How many feet?				
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG	
0	6	Topsoil & fine sand				
6	19	Soft brown clay				
19	29	Sand & gravel, fine to med.				
29	30	Brown clay				
30	38	Sand & gravel, fine to med.				
38	50	Soft sandy tan clay				
50	56	Sand & gravel, fine to med.				
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 1/6/86 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 2/4/86 under the business name of Clarke Well & Equip., Inc. by (signature) [Signature]						
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.						