

USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:		County <b>Reno</b>	Fraction <b>1/4 CN 1/4 SW 1/4</b>	Section number <b>22</b>	Township number <b>T 23 S R 6</b>	Range number <b>6 NW</b>
2. Distance and direction from nearest town or city: <b>1 mile West of South Hutchinson</b> Street address of well location if in city:			3. Owner of well: <b>Cities Service Gas Storage</b> R.R. or street: <b>Hutchinson, Kansas 67501</b> City, state, zip code:			
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: <b>Replacement Well No. 4</b>		6. Bore hole dia. <b>30"</b> in. Completion date _____ Well depth <b>45</b> ft.		
5. Type and color of material		From	To	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary		
Red-brown clay		0	5	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input checked="" type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Sandy red-brown clay		5	22	9. Casing: Material <b>Stl.</b> Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>60</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>43.77</b> lbs./ft. Dia. <b>12</b> in. to <b>40</b> ft. depth Wall Thickness: inches or Dia. _____ in. to _____ ft. depth gage No. <b>330"</b>		
Med. to coarse sand & gravel		22	37	10. Screen: Manufacturer's name <b>Layne</b> Type <b>St. Stl.</b> Dia. <b>12"</b> Slot/gauze <b>#5</b> Length <b>10'</b> Set between <b>35</b> ft. and <b>45</b> ft. Gravel pack? <b>yes</b> Size range of material <b>1/8x1/2</b>		
Slight clay streak		37	38	11. Static water level: _____ mo./day/yr. <b>20.5</b> ft. below land surface Date <b>7/28/77</b>		
Med. to coarse sand & gravel		38	47	12. Pumping level below land surfaces: <b>Not Test</b> _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield <b>300</b> g.p.m.		
				13. Water sample submitted: _____ mo./day/yr. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____		
				14. Well head completion: _____ Pitless adapter <b>60</b> inches above grade		
				15. Well grouted? <b>yes</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>20</b> ft.		
				16. Nearest source of possible contamination: _____ ft. _____ Direction <b>All</b> Type _____ Well disinfected upon completion? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		
				17. Pump: _____ Not installed Manufacturer's name <b>Layne &amp; Bauer</b> Model number <b>BRK</b> HP <b>15</b> Volts <b>440</b> Length of drop pipe <b>40</b> ft. capacity <b>300</b> g.p.m. Type: _____ <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
		(Use a second sheet if needed)				
18. Elevation: Tapography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input checked="" type="checkbox"/> Valley		19. Remarks: <b>This Well replaces a deeper well because softer water is obtained from shallower wells &amp; more water of better quality was needed for cooling purposes.</b>		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne Western Co. 102</b> Business name _____ License No. _____ Address <b>Wichita, Kansas</b> Signed <b>[Signature]</b> Date <b>8/9/77</b> Authorized representative		