

1 LOCATION OF WATER WELL: Harvey		FRACTION SE 1/4 SE 1/4 NW 1/4		SECTION NUMBER 35		TOWNSHIP NUMBER T 24 S		RANGE NUMBER R 1W E/W	
Distance and direction from nearest town or city street address of well if located within city? 1 mile E. of West St., 1 mile N. of 125th N., East on 7th St. 1/2 mile Sedgwick, Kansas									
2 WATER WELL OWNER: CLARK, Terry		Board of Agriculture, Division of Water Resource							
RR#,ST. ADDRESS,BOX #: 2032 E. 7th		CITY, STATE: Sedgwick, Kansas		ZIP CODE:		Application Number:			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL: 100 ft. ELEVATION: Depth of groundwater Encountered: ft. WELL'S STATIC WATER LEVEL 27 FT. BELOW LAND SURFACE MEASURED ON 11/23/04 Pump test data: Well water was ft. after hours of pumping @ gpm Est. Yield: gpm Well water was ft. after hours of pumping @ gpm Bore Hole Diameter 12 in. to 100 ft. and in. to ft. WELL WATER TO BE USED AS: ☒ 1. Domestic ☐ 3. Feedlot ☐ 5. Public water supply ☐ 7. Lawn and garden only ☐ 9. Dewatering ☐ 11. Injection well ☐ 2. Irrigation ☐ 4. Industrial ☐ 6. Oil field water supply ☐ 8. Air conditioning ☐ 10. Monitoring well ☐ 12. Other (Specify below) Was a chemical/bacteriological sample submitted to Department? YES ☒ NO ; If yes, what mo/day/yr was sample submitted YES ☒ NO							
5 TYPE OF CASING USED: 1. Steel 3. RPM (SR) 5. Wrought Iron 7. Fiberglass 9. Other (Specify below) CASING JOINTS: ☒ Glued Threaded ☒ 2. PVC ☐ 4. ABS ☐ 6. Asbestos-Cement ☐ 8. Concrete tile SDR-26 Welded Clamped Blank casing diameter 5 in. to 50 ft., Dia. in. to ft., Dia. in. to ft. Casing height above land surface: 16 in., Weight: 2.35 lbs. / ft. Wall thickness or gauge No. .214 TYPE OF SCREEN OR PERFORATION MATERIAL: 1. Steel 3. Stainless Steel 5. Fiberglass ☒ 7. PVC 9. ABS 11. Other (specify) 2. Brass 4. Galvanized 6. Concrete Tile 8. RMP (SR) 10. Asbestos-Cement 12. None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1. Continuous slot 3. Mill slot 5. Gauzed wrapped 7. Torch cut 9. Drilled holes 11. None (open hole) 2. Louvered shutter 4. Key punched 6. Wire wrapped ☒ 8. Saw cut 10. Other (specify) SCREEN - PERFORATION INTERVAL From 50 ft. to 100 ft., From ft. to ft. GRAVEL PACK INTERVALS: From 24 ft. to 40 ft., From 50 ft. to 100 ft. From ft. to ft., From ft. to ft.									
6 GROUT MATERIALS: 1. Neat cement 2. Cement Grout 3. Bentonite Other bentonite hole plug Grout Intervals: From 4 ft. to 24 ft., From 40 ft. to 50 ft., From ft. to ft. What is the nearest source of possible contamination: 1. Septic tank 4. Lateral lines 7. Pit privy 10. Livestock pens 13. Insecticide storage 15. Oil well/Gas well 2. Sewer lines 5. Cess Pool ☒ 8. Sewage lagoon 11. Fuel storage 14. Abandon water well 16. Other (specify below) 3. Watertight sewer line 6. Seepage pit 9. Feed yard 12. Fertilizer storage Direction from well? Southwest How many feet? 150									
From To LITHOLOGIC LOG From To LITHOLOGIC LOG 0 4 topsoil 4 15 clay 15 40 fine sand with clay streaks 40 47 clay 47 93 shale 93 95 limestone 95 100 shale									
7 Contractor's or Landowner's Certification: This water well was 1. ☒ constructed 2. reconstructed or 3. plugged under my jurisdiction and was completed on (mo/day/year) 11/23/2004 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 236 This water well record was completed on (mo/day/year) 11/24/2004 under the business name of Harp Well & Pump Service Inc. by (signature) <i>J o d d S. H a r p</i>									