

1 LOCATION OF WATER WELL		Fraction	Section Number	Township Number	Range Number
County: <u>Stafford</u>		$\frac{1}{4}$ <u>C</u> $\frac{1}{4}$ <u>NW</u> $\frac{1}{4}$	<u>19</u>	T <u>24</u> S	R <u>11</u> E/W
Distance and direction from nearest town or city? <u>from Stafford</u> <u>3/4 E 1/4 S 1/4 E</u>			Street address of well if located within city?		


2 WATER WELL OWNER: <u>Virgil Rice</u>		Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: <u>Rt 1</u>		Application Number: <u>33852</u>
City, State, ZIP Code: <u>Stafford, Ks. 67578</u>		

3 DEPTH OF COMPLETED WELL: <u>84</u> ft. Bore Hole Diameter: <u>29</u> in. to <u>84</u> ft. and _____ in. to _____ ft.	
Well Water to be used as:	
1 Domestic 3 Feedlot 2 Irrigation 4 Industrial	5 Public water supply 6 Oil field water supply 7 Lawn and garden only
8 Air conditioning 9 Dewatering 10 Observation well 11 Injection well 12 Other (Specify below)	
Well's static water level: <u>19</u> ft. below land surface measured on <u>10</u> month <u>3</u> day <u>80</u> year	
Pump Test Data	Well water was: <u>48 1/2</u> ft. after <u>1</u> hours pumping <u>800</u> gpm
Est. Yield <u>1,000</u> gpm	Well water was: <u>53</u> ft. after <u>2</u> hours pumping <u>1,000</u> gpm

4 TYPE OF BLANK CASING USED:		5 Wrought iron		8 Concrete tile		Casing Joints: Glued _____ Clamped _____	
1 Steel 2 PVC		3 RMP (SR) 4 ABS		6 Asbestos-Cement 7 Fiberglass		9 Other (specify below) Welded ☒ ThREADED	
Blank casing dia: <u>16</u> in. to <u>48</u> ft. Dia _____ in. to _____ ft. Dia _____ in. to _____ ft.		Casing height above land surface: <u>18</u> in. weight _____ lbs./ft. Wall thickness or gauge No. <u>7</u>					
TYPE OF SCREEN OR PERFORATION MATERIAL:				7 PVC			
1 Steel 2 Brass				10 Asbestos-cement 11 Other (specify) _____			
3 Stainless steel 4 Galvanized steel				8 RMP (SR) 12 None used (open hole)			
5 Fiberglass				9 ABS			
6 Concrete tile				11 None (open hole)			
Screen or Perforation Openings Are:				5 Gauzed wrapped			
1 Continuous slot 2 Louvered shutter				6 Wire wrapped 7 Torch cut			
3 Mill slot 4 Key punched				8 Saw cut 9 Drilled holes 10 Other (specify) _____			
Screen-Perforation Dia: <u>16</u> in. to <u>84</u> ft. Dia _____ in. to _____ ft.		Screen-Perforated Intervals:		From <u>48</u> ft. to <u>84</u> ft.		From _____ ft. to _____ ft.	
Gravel Pack Intervals:		From <u>10</u> ft. to <u>90</u> ft.		From _____ ft. to _____ ft.		From _____ ft. to _____ ft.	

5 GROUT MATERIAL:		1 Neat cement		2 Cement grout		3 Bentonite		4 Other _____	
Grouted Intervals: From <u>0</u> ft. to <u>10</u> ft.		From _____ ft. to _____ ft.		From _____ ft. to _____ ft.		From _____ ft. to _____ ft.		From _____ ft. to _____ ft.	
What is the nearest source of possible contamination:									
1 Septic tank 2 Sewer lines 3 Lateral lines		4 Cess pool 5 Seepage pit 6 Pit privy		7 Sewage lagoon 8 Feed yard 9 Livestock pens		10 Fuel storage 11 Fertilizer storage 12 Insecticide storage 13 Watertight sewer lines		14 Abandoned water well 15 Oil well/Gas well 16 Other (specify below) _____	
Direction from well: <u>West</u>		How many feet: <u>1300</u>		Water Well Disinfected? Yes <u>HTH</u> No _____					
Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, date sample was submitted _____ month _____ day _____ year: Pump Installed? Yes ☒ No _____									
If Yes: Pump Manufacturer's name: <u>Western Land Roller</u> Model No. <u>3stage 12CM</u> HP <u>40</u> Volts <u>460</u>									
Depth of Pump Intake: <u>70</u> ft. Pumps Capacity rated at <u>800</u> gal./min.									
Type of pump: 1 Submersible 2 Turbine 3 Jet 4 Centrifugal 5 Reciprocating 6 Other _____									

6 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on _____ month <u>23</u> day <u>81</u> year <u>19</u>					
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>134</u>					
This Water Well Record was completed on _____ month <u>27</u> day <u>81</u> year under the business name of <u>Rosenkrantz - Bemis</u> by (signature) <u>Lore Dodson</u>					

7 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 	FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
	0	3	Top soil			
	3	11	Sandy brown clay			
	11	25	Sandy brown & gray clay			
	25	33	Sandy brown, gray & white clay			
	33	53	Sand & gravel			
	53	65	Sandy clay, sand & gravel			
	65	84	fine sand & gravel			
84	90	Sandy brown clay				

ELEVATION:	
Depth(s) Groundwater Encountered 1. <u>19</u> ft. 2. _____ ft. 3. _____ ft. 4. _____ ft.	(Use a second sheet if needed)

INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.