


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County STafford	Township name Fairview	Fraction NWNE	Section number 24	Town number T24S	Range number R11W
Distance and direction from nearest town or city: 3 1/4 mi W of Sylvia, Kans.				3 Owner of well: Earl Hayes Address: R.R. Sylvia, Kans.		
Locate with "X" in section below: 				Sketch map: 4 Well depth: 61 ft. Date of completion 8-30-75 Well diameter 10 in.		
2 Type and color of material				From	To	5 ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Sandy top soil				0	3	6 Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☐
Brown dirt				3	8	7 Casing: Material RMP Height: 12 in. Threaded ☐ Welded ☐ Surface ☐ Dia. 6 in. Weight 200 lbs./ft. Diam. 6 in. to 61 ft. depth Drive shoe? ☐ Yes ☒ No
sand				8	13	8 Screen: Manufacturer Jess+howell Type RMP Dia. 6" Slot gauge 3/16" Length 10' Set between 5 ft. and 61 ft. Fittings: no gravel Gravel pack ☒ Yes ☐ No Size range of material
gray clay				13	18	9 Static water level: 36 ft. below land surface Date 8-30-75
sand				18	47	10 Pumping level below land surfaces: 46 ft. after 1 hrs. pumping 20 g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 35 g.p.m.
sand + gravel				47	61	11 Water sample submitted: ☐ Yes ☒ No Date
						12 Well head completion: ☒ Pitless adapter ☐ Inches above grade
						13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ Depth: From 4 ft. to 14 ft.
						14 Nearest source of possible contamination: ft. 200 Direction E Type Septic Well disinfected upon completion? ☒ Yes ☐ No
						15 Pump: ☐ Not installed Manufacturer's name Aermotor Model number SD12 HP 1/2 Volts 230V Length of drop pipe 47 ft. capacity 12 g.m.p. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(use a second sheet if needed)						
16 Remarks: elevation Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Miller Water Well 137 Business name Hutchinson, Ks. License No. Address Joe Miller Date 9-1-75 Signed Joe Miller Authorized representative		

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5