

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: Stafford		NE 1/4 NE 1/4 SW 1/4	13	T 24 S	R 12 NEW
Distance and direction from nearest town or city street address of well if located within city? 220 Camden St. Stafford, Ks.					
2 WATER WELL OWNER: Loren Harris		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # : P.O. Box 122		Application Number:			
City, State, ZIP Code : Sylva, Ks. 67581					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 95 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 18 1/2 ft. below land surface measured on mo/day/yr 8-17-99			
		Pump test data: Well water was ft. after hours pumping gpm			
		Est. Yield NA gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter 9 7/8 in. to 95 ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes HTH No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued X Clamped			
1 Steel 3 RMP (SR)		Welded			
2 PVC 4 ABS		Threaded			
5 Wrought iron					
6 Asbestos-Cement					
7 Fiberglass					
Blank casing diameter 5 in. to 75 ft., Dia		in. to ft., Dia			
Casing height above land surface 24 in., weight SDR 26 lbs./ft.		Wall thickness or gauge No.			
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel		8 RMP (SR) 11 Other (specify)			
2 Brass 4 Galvanized steel		9 ABS 12 None used (open hole)			
6 Concrete tile					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot		9 Drilled holes			
2 Louvered shutter 4 Key punched		10 Other (specify)			
SCREEN-PERFORATED INTERVALS:		From 75 ft. to 95 ft., From ft. to ft.			
		From ft. to ft., From ft. to ft.			
GRAVEL PACK INTERVALS:		From 95 ft. to 20 ft., From ft. to ft.			
		From ft. to ft., From ft. to ft.			
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout 3 Bentonite 4 Other Hole plug			
Grout Intervals: From 20 ft. to 0 ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy		11 Fuel storage 15 Oil well/Gas well			
2 Sewer lines 5 Cess pool 8 Sewage lagoon		12 Fertilizer storage 16 Other (specify below)			
3 Watertight sewer lines 6 Seepage pit 9 Feedyard		13 Insecticide storage House			
Direction from well? West		How many feet? 35			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Top soil	77	85	Sand and gravel medium loose
3	6	Brown clay	85	86	Brown clay
6	18	Tough sticky gray and brown clay	86	95	Sand and gravel medium loose clean
18	25	Fine sand and sandy brown and gray clay			
25	33	Brown and white clay, white rock			
33	35	Sandy brown clay			
35	42	Brown and white clay			
42	45	Sandy brown clay			
45	53	Sand and gravel medium tight			
53	62	Sticky redish brown clay			
62	67	Sand and gravel medium lot of caliche			
67	73	Brown and white clay hard rock			
73	77	Sandy clay and fine sand			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8-17-99 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134 . This Water Well Record was completed on (mo/day/yr) 9-7-99 under the business name of Rosencrantz-Bemis by (signature) <i>Freddie Adson</i>					