

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number																																																																																					
County: Stafford		SW 1/4 NE 1/4 NW 1/4		13		T 24 S		R 12 E (W)																																																																																					
Distance and direction from nearest town or city street address of well if located within city? Northeast of the intersection of Vickers & Buckeye																																																																																													
2 WATER WELL OWNER: City of Stafford RR#, St. Address, Box #: P.O. Box 280 City, State, ZIP Code: Stafford, KS 67578 Board of Agriculture, Division of Water Resources Application Number: 35,315																																																																																													
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 137.57 ft. ELEVATION: unknown																																																																																											
		Depth(s) Groundwater Encountered 1 _____ ft. 2 _____ ft. 3 _____ ft. WELL'S STATIC WATER LEVEL 20.5 ft. below land surface measured on mo/day/yr 12-5-03 Pump test data: Well water was not checked ft. after _____ hours pumping _____ gpm Est. Yield unknown gpm: Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter 36 in. to 137 ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: (5) Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr sample was sub- mitted Water Well Disinfected? Yes ☒ No																																																																																											
		5 TYPE OF BLANK CASING USED: 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued _____ Clamped _____ (1) Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded ☒ 2 PVC 4 ABS 7 Fiberglass Threaded _____ Blank casing diameter 12 3/4 in. to 76.02 ft., Dia 12 3/4 in. to 114.25 ft., Dia 12 3/4 in. to 136.57 ft. Casing height above land surface 12 in., weight 49.56 lbs./ft. Wall thickness or gauge No .375																																																																																											
		TYPE OF SCREEN OR PERFORATION MATERIAL: 7 PVC 10 Asbestos-cement 1 Steel (3) Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 5 Gauzed wrapped 8 Saw cut 11 None (open hole) (1) Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) _____ ft.																																																																																											
		SCREEN-PERFORATED INTERVALS: From 76.02 ft. to 96.25 ft., From _____ ft. to _____ ft. From 114.25 ft. to 134.37 ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 71 ft. to 103 ft., From _____ ft. to _____ ft. From 107 ft. to 137 ft., From _____ ft. to _____ ft.																																																																																											
		6 GROUT MATERIAL: 1 Neat cement (2) Cement grout 3 Bentonite 4 Other 50% Bentonite Holeplug & 50% Sand Grout Intervals: From 0 ft. to 27 ft., From 103 ft. to 107 ft., From 27 ft. to 71 ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage None known Direction from well? _____ How many feet? _____																																																																																											
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>0</td><td>5</td><td>Topsoil</td><td></td><td></td><td></td></tr> <tr><td>5</td><td>8</td><td>Clay, brown</td><td></td><td></td><td></td></tr> <tr><td>8</td><td>43</td><td>Clay and streaks of sand</td><td></td><td></td><td></td></tr> <tr><td>43</td><td>48</td><td>Sand and gravel, fine, medium</td><td></td><td></td><td></td></tr> <tr><td>48</td><td>76</td><td>Clay, tan and caliche</td><td></td><td></td><td></td></tr> <tr><td>76</td><td>96</td><td>Sand and gravel, fine, medium</td><td></td><td></td><td></td></tr> <tr><td>96</td><td>104</td><td>Clay, tan</td><td></td><td></td><td></td></tr> <tr><td>104</td><td>107</td><td>Clay and some sand streaks</td><td></td><td></td><td></td></tr> <tr><td>107</td><td>113</td><td>Clay, reddish brown</td><td></td><td></td><td></td></tr> <tr><td>113</td><td>122</td><td>Sandstone, red</td><td></td><td></td><td></td></tr> <tr><td>122</td><td>128</td><td>Clay, brown</td><td></td><td></td><td></td></tr> <tr><td>128</td><td>135</td><td>Sand and gravel, fine, medium</td><td></td><td></td><td></td></tr> <tr><td>135</td><td>137</td><td>Shale, red, hard</td><td></td><td></td><td></td></tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	5	Topsoil				5	8	Clay, brown				8	43	Clay and streaks of sand				43	48	Sand and gravel, fine, medium				48	76	Clay, tan and caliche				76	96	Sand and gravel, fine, medium				96	104	Clay, tan				104	107	Clay and some sand streaks				107	113	Clay, reddish brown				113	122	Sandstone, red				122	128	Clay, brown				128	135	Sand and gravel, fine, medium				135	137	Shale, red, hard			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																																																								
0	5	Topsoil																																																																																											
5	8	Clay, brown																																																																																											
8	43	Clay and streaks of sand																																																																																											
43	48	Sand and gravel, fine, medium																																																																																											
48	76	Clay, tan and caliche																																																																																											
76	96	Sand and gravel, fine, medium																																																																																											
96	104	Clay, tan																																																																																											
104	107	Clay and some sand streaks																																																																																											
107	113	Clay, reddish brown																																																																																											
113	122	Sandstone, red																																																																																											
122	128	Clay, brown																																																																																											
128	135	Sand and gravel, fine, medium																																																																																											
135	137	Shale, red, hard																																																																																											
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed or (3) plugged under my jurisdiction and was completed on (mo/day/year) 12-5-03 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No 185 This Water Well Record was completed on (mo/day/yr) 12-31-03 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>																																																																																													
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.																																																																																													