

WATER WELL RECORD

Form WWC-5

Division of Water Resources; App. No.

5936

1 LOCATION OF WATER WELL:

County: Stafford

Fraction

1/4 NC 1/4 SW 1/4

Section Number

9

Township Number

T 24 S

Range Number

R 12 E (W)Distance and direction from nearest town or city street address of well if located within city? Approximately 2 1/4 miles west and 1/4 mile north of Stafford

Global Positioning Systems (decimal degrees, min. of 4 digits)

Latitude: 37.973344Longitude: -98.650373Elevation: UnknownDatum: NAD83Data Collection Method: WAAS GPS Unit

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

N

--NW--		--NE--
--SW--		--SE--

S

4 DEPTH OF COMPLETED WELL

110 ft.

Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft.

WELL'S STATIC WATER LEVEL 24 ft. below land surface measured on mo/day/yr. 03-11-08Pump test data: Well water was Not checked ft. after _____ hours pumping _____ gpmEst. Yield Unknown gpm: Well water was _____ ft. after _____ hours pumping _____ gpm

WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well

1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)

(2) Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr _____Sample was submitted _____ Water well disinfected? Yes ☒ No _____

5 TYPE OF CASING USED:

1 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below)

(2) PVC 4 ABS 7 Fiberglass

CASING JOINTS: Glued ☒ Clamped _____

Welded _____

Threaded _____

Blank casing diameter 16 in. to 65 ft., Diameter 16 in. to 74 - 89 ft., Diameter _____ in. to _____ ft.Casing height above land surface 12 in., weight 19.75 lbs./ft. Wall thickness or gauge No. .616

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel (3) Stainless Steel 5 Fiberglass 7 PVC 9 ABS 11 Other (Specify) _____

2 Brass 4 Galvanized Steel 6 Concrete tile 8 RM (SR) 10 Asbestos-Cement 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

(1) Continuous slot 3 Mill slot 5 Gauzed wrapped 7 Torch cut 9 Drilled holes 11 None (open hole)

2 Louvered shutter 4 Key punched 6 Wire wrapped 8 Saw Cut 10 Other (Specify) _____

SCREEN-PERFORATED INTERVALS: From 65 ft. to 74 ft., From _____ ft. to _____ ft.From 89 ft. to 109 ft., From _____ ft. to _____ ft.GRAVEL PACK INTERVALS: From 22 ft. to 80 ft., From _____ ft. to _____ ft.From 80 ft. to 109 ft., From _____ ft. to _____ ft.

6 GROUT MATERIAL: 1 Neat Cement 2 Cement grout 3 Bentonite (4) Other _____ Concrete Grout

Grout Intervals: From _____ ft. to _____ ft., From _____ ft. to _____ ft., From 3 ft. to 22 ft.

What is the nearest source of possible contamination:

1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 13 Insecticide Storage (16) Other (specify below)

2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 14 Abandoned water well

3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer Storage 15 Oil well/gas well

None known

Direction from well? _____

How many feet? _____

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Topsoil	93	109	Sand and gravel, fine, medium, coarse
3	10	Clay, brown			
10	29	Clay, gray			
29	35	Clay, brown			
35	44	Sand, very fine			
44	73	Sand and gravel, fine, medium, coarse, clay streaks at 62', thin			
73	76	Sand, fine, some clay			
76	82	Clay, gray			
82	88	Clay, brown			
88	93	Sand and gravel, fine, medium			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed (3) plugged under my jurisdiction and was completed on (mo/day/year) 03-11-08 and this record is true to the best of my knowledge and belief.Kansas Water Well Contractor's License No. 771 This Water Well Record was completed on (mo/day/year) 3-24-08Under the business name of Clarke Well & Equipment, Inc. by (signature) [Signature]

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.