

374 12481 Stock
WATER WELL RECORD**Form WWC-5**Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Stafford		Fraction 1/4 SE 1/4 SW 1/4 SW 1/4	Section Number 6	Township No. T 24 S	Range Number R 12 E W																																																																		
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ Approximately 0.5 miles south and 4 miles east of St. John.			Global Positioning System (GPS) information: Latitude: 37.984708 (in decimal degrees) Longitude: -98.68824 (in decimal degrees) Elevation: Unknown Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: WAAS) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																				
2 WATER WELL OWNER: Steve Jones RR#, Street Address, Box #: 112 N. Gray St. City, State, ZIP Code: St. John, KS 67576																																																																							
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W <table border="1" style="display: inline-table; border-collapse: collapse;"><tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr><tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr><tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr><tr><td style="width: 20px; height: 20px;"></td><td style="width: 20px; height: 20px;"></td></tr></table> E S -----1 mile-----										4 DEPTH OF COMPLETED WELL 75 ft. Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft. WELL'S STATIC WATER LEVEL 24 ft. below land surface measured on mo/day/yr 07/26/13 Pump test data: Well water was not checked ft. after _____ hours pumping _____ gpm EST. YIELD _____ gpm. Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter 9 in. to 75 ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☒ Other (Specify below) Stock ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted _____ Water well disinfected? ☒ Yes ☐ No																																																													
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 5 in. to 47 ft., Diameter 5 in. to 68 ft., Diameter _____ in. to _____ ft. Casing height above land surface 24 in., Weight 2.36 lbs./ft., Wall thickness or gauge No. 214 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 47 ft. to 57 ft., From 68 ft. to 73 ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 20 ft. to 75 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																																							
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other _____ Grout Intervals: From 0 ft. to 20 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) None Known ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well _____ Distance from well _____																																																																							
<table border="1" style="width: 100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th><th>FROM</th><th>TO</th><th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th></tr></thead><tbody><tr><td>0</td><td>4</td><td>Sand</td><td>57</td><td>61</td><td>Clay, brown, yellow, sandy</td></tr><tr><td>4</td><td>6</td><td>Clay, brown</td><td>61</td><td>68</td><td>Sand, very fine</td></tr><tr><td>6</td><td>9</td><td>Clay, gray</td><td>68</td><td>73</td><td>Sand, gravel, fine to medium</td></tr><tr><td>9</td><td>15</td><td>Clay, gray, sandy</td><td>73</td><td>75</td><td>Clay, yellow, caliche</td></tr><tr><td>15</td><td>19</td><td>Clay, gray, white, caliche</td><td></td><td></td><td></td></tr><tr><td>19</td><td>22</td><td>Clay, white, gray, sand streaks</td><td></td><td></td><td></td></tr><tr><td>22</td><td>39</td><td>Sand, gravel, fine to coarse</td><td></td><td></td><td></td></tr><tr><td>39</td><td>46</td><td>Clay, brown</td><td></td><td></td><td></td></tr><tr><td>46</td><td>49</td><td>Clay, yellow</td><td></td><td></td><td></td></tr><tr><td>49</td><td>57</td><td>Sand, gravel, fine to coarse, yellow clay</td><td></td><td></td><td></td></tr></tbody></table>						FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	4	Sand	57	61	Clay, brown, yellow, sandy	4	6	Clay, brown	61	68	Sand, very fine	6	9	Clay, gray	68	73	Sand, gravel, fine to medium	9	15	Clay, gray, sandy	73	75	Clay, yellow, caliche	15	19	Clay, gray, white, caliche				19	22	Clay, white, gray, sand streaks				22	39	Sand, gravel, fine to coarse				39	46	Clay, brown				46	49	Clay, yellow				49	57	Sand, gravel, fine to coarse, yellow clay			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																		
0	4	Sand	57	61	Clay, brown, yellow, sandy																																																																		
4	6	Clay, brown	61	68	Sand, very fine																																																																		
6	9	Clay, gray	68	73	Sand, gravel, fine to medium																																																																		
9	15	Clay, gray, sandy	73	75	Clay, yellow, caliche																																																																		
15	19	Clay, gray, white, caliche																																																																					
19	22	Clay, white, gray, sand streaks																																																																					
22	39	Sand, gravel, fine to coarse																																																																					
39	46	Clay, brown																																																																					
46	49	Clay, yellow																																																																					
49	57	Sand, gravel, fine to coarse, yellow clay																																																																					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 07/26/13 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 08/09/13 under the business name of Clarke Well & Equipment, Inc. by (signature) _____																																																																							
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																							