


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County STAFFORD	Township name STAFFORD	Fraction 7N/5E/5E	Section number 14	Town number T245	Range number R12W
Distance and direction from nearest town or city: 5 BLK West on Morrell St			3 Owner of well: Jim Henry			
Street address of well location if in city: W. Morrell - STAFFORD			Address: W. Morrell STAFFORD, Kans. 67578			
Locate with "X" in section below: N  W E S 1 Mile			Sketch map:			4 Well depth: 135 ft. Date of completion 9-20-75 Well diameter 5 in.
2 Type and color of material			Fram		To	
			Earth		0 5	
Hard brown clay			5		20	
Sandy Clay			20		30	
Yellow Clay			30		46	
Quick sand & Fine Sand			46		50	
White clay & gyp			50		72	
Fine sand			72		75	
Clay & rock strips			75		115	
Sand			115		118	
Clay			118		123	
Rock			123		128	
Coarse gravel			128		135	
(use a second sheet if needed)						
16 Remarks: elevation Flat Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Hank Bruce Well Serv. 103 Business name 1117 STOUT License No. Address Wayne Bruce Signed Wayne Bruce Date 9-20-75 Authorized representative			
15 Pump: Manufacturer's name STO-RITE Model number LP5C2 HP 1/2 Volts 230 Length of drop pipe 40 ft. capacity 30 g.m.p. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other			14 Nearest source of possible contamination: ft. 60 Direction SE Type Septic Tank Well disinfected upon completion? ☒ Yes ☐ No			
13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ Depth: From 4 ft. to 14 ft.			12 Well head completion: ☒ Pitless adapter ☐ Inches above grade			
11 Water sample submitted: ☐ Yes ☒ No Date			10 Pumping level below land surfaces: ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 100 g.p.m.			
9 Static water level: 23 ft. below land surface Date 9-20-75			8 Screen: Manufacturer Jess + Lowell Type RMP Dia. 5" Slot/gauze 1/16 Length 20' Set between 115 ft. and 135 ft. Fittings: Gravel pack ☒ Yes ☐ No Size range of material 1/16-3/8			
6 Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well			5 ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5