


1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Stafford	NE 1/4 NE 1/4 SW 1/4	2	T 24 S	R 13 E (W)

Distance and direction from nearest town or city street address of well if located within city?

Stafford County Landfill

2 WATER WELL OWNER:	Stafford County	01968014	MW-5
RR#, St. Address, Box #	209 North Broadway	Board of Agriculture, Division of Water Resources	
City, State, ZIP Code	St. John, Kansas 67576	Application Number:	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 50 ft. ELEVATION: Approx Surface 1910
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL ... 30 ... ft. below land surface measured on mo/day/yr 05/23/96 Pump test data: Well water was ft. after hours pumping gpm Est. Yield N/A ... gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter ... 8.25 in. to ... 50 ... ft., and ... in. to ... ft. WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes No X If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No X

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued Clamped	
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded
2 PVC	4 ABS	7 Fiberglass		Threaded. X
Blank casing diameter ... 2 ... in. to ... 40 ... ft., Dia. in. to ... ft., Dia. in. to ... ft.				
Casing height above land surface ... 36 ... in., weight ... lbs./ft. Wall thickness or gauge No. Schedule 40				
TYPE OF SCREEN OR PERFORATION MATERIAL:	7 PVC	10 Asbestos-cement		
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)	11 Other (specify)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS	12 None used (open hole)
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)	
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes	
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)	
SCREEN-PERFORATED INTERVALS: From ... 40 ... ft. to ... 50 ... ft., From ... ft. to ... ft.				
GRAVEL PACK INTERVALS: From ... 38 ... ft. to ... 50 ... ft., From ... ft. to ... ft.				

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other	
Grout Intervals: From ... 0 ... ft. to ... 36 ... ft., From ... 36 ... ft. to ... 38 ... ft., From ... ft. to ... ft.					
What is the nearest source of possible contamination:	1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
	2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
	3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well?				13 Insecticide storage	

FROM		TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	1.0		Fine Sand, Brown			
1.0	2.0		Fine Sand, Gray to Dark Brown			
2.0	8.0		Fine Sand, Brown			
8.0	13.0		Fine Sand, Gray-Brown			
13.0	26.0		Fine Sand, Light Brown			
26.0	29.0		Clayey Fine Sand, Light Brown			
29.0	36.0		Fine Sand, Brown			
36.0	48.0		Clayey, Fine to Medium Sand, Brown			
48.0	50.0		Sandy Fat Clay, Red-Brown to Brown			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was 1 constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 05/22/96 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 416 This Water Well Record was completed on (mo/day/yr) 05-24-96 under the business name of Terracon Consultants, Inc. by (signature) <i>Steve Fischer</i>
--