

1 LOCATION OF WATER WELL:		Fraction 1/4 NC 1/4 SW 1/4		Section Number 25	Township Number T 24 S	Range Number R 13 E W
Distance and direction from nearest town or city street address of well if located within city? Approximately 5 3/4 miles west and 1 3/4 miles south of Stafford						
2 WATER WELL OWNER: Dudley Cattle Company, Inc. RR#, St. Address, Box # : P.O. Box 65 City, State, ZIP Code : St. John, KS 67576 Board of Agriculture, Division of Water Resources Application Number: 6,649						
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 140 ft. ELEVATION: unknown				
N ↑ 1 Mile ↓ S NW SW NE SE E →		Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft. ft.				
		WELL'S STATIC WATER LEVEL 28 ft. below land surface measured on mo/day/yr 4-15-03				
		Pump test data: Well water was not checked ft. after hours pumping gpm				
		Est. Yield unknown gpm: Well water was ft. after hours pumping gpm				
		Bore Hole Diameter 24 in. to 140 ft., and in. to ft.				
5 TYPE OF BLANK CASING USED:		5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped				
① Steel 3 RMP (SR)		6 Asbestos-Cement 9 Other (specify below) Welded ☒				
2 PVC 4 ABS		7 Fiberglass Threaded				
Blank casing diameter 16 in. to 99 ft., Dia in. to ft., Dia in. to ft.						
Casing height above land surface 12 in., weight 36.87 lbs./ft. Wall thickness or gauge No .219						
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement				
① Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)						
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)						
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)				
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes						
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) Bridge Slot						
SCREEN-PERFORATED INTERVALS: From 99 ft. to 139 ft., From ft. to ft.						
GRAVEL PACK INTERVALS: From 23 ft. to 140 ft., From ft. to ft.						
From ft. to ft., From ft. to ft.						
6 GROUT MATERIAL: 1 Neat cement ② Cement grout 3 Bentonite 4 Other						
Grout Intervals: From 0 ft. to 23 ft., From ft. to ft., From ft. to ft.						
What is the nearest source of possible contamination:						
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well						
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well						
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)						
13 Insecticide storage None known						
Direction from well? How many feet?						
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	
0	3	Topsoil				
3	23	Clay, sandy				
23	30	Sand, fine				
30	38	Sand and gravel, fine, medium				
38	39	Clay, tan				
39	58	Sand and gravel, fine, medium, some clay				
58	90	Clay				
90	94	Sand and gravel, fine, medium with clay				
94	100	Sand and gravel, fine, medium				
100	106	Sand and gravel, fine				
106	139	Sand and gravel, fine, medium				
139	140	Shale, red				
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ① constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 4-15-03 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No 185 This Water Well Record was completed on (mo/day/yr) 4-18-03 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment</i>						
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.						