

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

20,746

1 LOCATION OF WATER WELL: County: Stafford		Fraction 1/4 1/4 NC 1/4 NW 1/4		Section Number 15		Township No. T 24 S		Range Number R 13 ☐ E ☒ W																																																													
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ Approximately 2 miles south and 1 mile east of St. John.				Global Positioning System (GPS) information: Latitude: 37.96666 (in decimal degrees) Longitude: -98.742213 (in decimal degrees) Elevation: unknown Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: WAAS ☒ GPS unit (Make/Model: _____) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																	
2 WATER WELL OWNER: Soden Farm RR#, Street Address, Box #: 112 N. Gray City, State, ZIP Code : St. John, KS 67576																																																																					
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N <table border="1" style="margin: auto; border-collapse: collapse;"> <tr> <td style="padding: 5px;">--NW--</td> <td style="padding: 5px;">--NE--</td> </tr> <tr> <td style="padding: 5px;">--SW--</td> <td style="padding: 5px;">--SE--</td> </tr> </table> S --- 1 mile ---		--NW--	--NE--	--SW--	--SE--	4 DEPTH OF COMPLETED WELL 137.50 ft. Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft. WELL'S STATIC WATER LEVEL 23.50 ft. below land surface measured on mo/day/yr 10/10/12 Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm EST. YIELD _____ gpm. Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter 24 in. to 137 ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted _____ Water well disinfected? ☒ Yes ☐ No																																																															
--NW--	--NE--																																																																				
--SW--	--SE--																																																																				
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 76 ft., Diameter _____ in. to _____ ft., Diameter _____ in. to _____ ft. Casing height above land surface 18 in., Weight 19.75 lbs./ft., Wall thickness or gauge No. 616 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 76 ft. to 136 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 22 ft. to 137 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																																					
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 2 ft. to 22 ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well _____ Distance from well _____ None Known																																																																					
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>2</td> <td>Topsoil</td> <td>120</td> <td>136</td> <td>Sand & gravel, fine to coarse, caliche, clay streaks</td> </tr> <tr> <td>2</td> <td>8</td> <td>Clay, brown, sandy</td> <td></td> <td></td> <td></td> </tr> <tr> <td>8</td> <td>23</td> <td>Clay, gray</td> <td>136</td> <td>137</td> <td>Weathered shale, green & yellow</td> </tr> <tr> <td>23</td> <td>30</td> <td>Sand & gravel, fine to coarse</td> <td></td> <td></td> <td></td> </tr> <tr> <td>30</td> <td>65</td> <td>Sand & gravel, fine to medium, clay streaks</td> <td></td> <td></td> <td></td> </tr> <tr> <td>65</td> <td>75</td> <td>Sand & gravel, fine to coarse, clay streak</td> <td></td> <td></td> <td></td> </tr> <tr> <td>75</td> <td>78</td> <td>Sand & gravel, fine to medium</td> <td></td> <td></td> <td></td> </tr> <tr> <td>78</td> <td>79</td> <td>Clay, yellow</td> <td></td> <td></td> <td></td> </tr> <tr> <td>79</td> <td>120</td> <td>Sand & gravel, fine to coarse</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	2	Topsoil	120	136	Sand & gravel, fine to coarse, caliche, clay streaks	2	8	Clay, brown, sandy				8	23	Clay, gray	136	137	Weathered shale, green & yellow	23	30	Sand & gravel, fine to coarse				30	65	Sand & gravel, fine to medium, clay streaks				65	75	Sand & gravel, fine to coarse, clay streak				75	78	Sand & gravel, fine to medium				78	79	Clay, yellow				79	120	Sand & gravel, fine to coarse			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																
0	2	Topsoil	120	136	Sand & gravel, fine to coarse, caliche, clay streaks																																																																
2	8	Clay, brown, sandy																																																																			
8	23	Clay, gray	136	137	Weathered shale, green & yellow																																																																
23	30	Sand & gravel, fine to coarse																																																																			
30	65	Sand & gravel, fine to medium, clay streaks																																																																			
65	75	Sand & gravel, fine to coarse, clay streak																																																																			
75	78	Sand & gravel, fine to medium																																																																			
78	79	Clay, yellow																																																																			
79	120	Sand & gravel, fine to coarse																																																																			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 10/10/12 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 10/11/12 under the business name of Clarke Well & Equipment, Inc. by (signature) _____																																																																					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																					