


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Stafford	Township name	Fraction Q NW 1/4	Section number 2	Town number 245	Range number 14N	
Distance and direction from nearest town or city: 4 W.			3 Owner of well: MRS. W. H. Dudley				
Street address of well location if in city: St. John, KS			Address: St. John, KS				
Locate with "X" in section below: 			Sketch map:			4 Well depth: 86 ft. Date of completion 7-22-75 Well diameter 30 in.	
2 Type and color of material			From			To	
			Top Soil - Clay			0	32
			Sandy Clay			32	50
			Clay			50	58
			Sand - Gravel			58	86
						5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
						6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☐	
						7 Casing: Material IRON Height: above below Threaded ☐ Welded ☒ Surface 12 in. Diam. 16 in. to 16 in. depth 16 in. to 16 in. depth Drive shoe? ☐ Yes ☒ No	
						8 Screen: Manufacturer Doerr's Type IRON Dia. 16" Slot/gauze 1/8" Length 20' Set between 66" ft. and 86" ft. Fittings: 1/8" - 3/4" Gravel pack ☒ Yes ☐ No Size range of material	
						9 Static water level: 30 ft. below land surface Date 7-22-75	
						10 Pumping level below land surfaces: 58 ft. after 3 hrs. pumping 1000 g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield 1000 g.p.m.	
						11 Water sample submitted: ☒ Yes ☐ No Date	
						12 Well head completion: ☐ Pitless adapter ☒ Inches above grade 12	
						13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ Depth: From 0 ft. to 10 ft.	
						14 Nearest source of possible contamination: None ft. Direction Type Well disinfected upon completion? ☐ Yes ☒ No	
						15 Pump: ☐ Not installed Manufacturer's name Goulds Model number 4-12510 60 Volts Length of drop pipe 70 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
16 Remarks: elevation			17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Kelly's Water Well Serv. Inc. 186 Business name R 2 Great Bend KS License No. Address Kelly Price Date 8-16-75 Signed Kelly Price Authorized representative				

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5