


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction 1/4 1/4 CSE 1/4	Section number 8	Township number T 24 S	Range number R 14 E W
2. Distance and direction from nearest town or city: 5 1/2 mi. Northeast of Macksville, KS Street address of well location if in city:				3. Owner of well: Hugh A. McCandless R.R. or street: 308 W. 4th City, state, zip code: St. John, KS 67576		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 24 in. Completion date 7-3-75 Well depth 107 ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From	To	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Top soil		0	3	9. Casing: Material Steel Height Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 60 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.		
Brown & gray gray clay, sand & limestone streaks		3	45	10. Screen: Manufacturer's name _____ Type Double-slot Dia. 16" Slot gauge 1/8 Length 47' Set between 60 ft. and 107 ft. ft. and _____ ft. Gravel pack? Yes Size range of material 3/8-200		
Sand & fine gravel		45	49	11. Static water level: _____ mo./day/yr. 31 ft. below land surface Date 7-3-75		
Brown & gray clay & limestone		49	57	12. Pumping level below land surfaces: N/C _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.		
Sand & gravel		57	80	13. Water sample submitted: _____ mo./day/yr. Yes ☒ No ☐ Date _____		
Green clay, limestone & gravel streaks		80	83	14. Well head completion: _____ Pitless adapter 12 inches above grade		
Sand & gravel		83	102	15. Well grouted? Yes With: ☒ Neat cement _____ Bentonite _____ Concrete _____ Depth: From 0 ft. to 10 ft.		
Sand, gravel & cemented streaks		102	106	16. Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? _____ Yes ☒ No ☐		
Pink clay		106	107	17. Pump: _____ Not installed Manufacturer's name FMC Corp. Model number 12LB-3 HP 80 Volts _____ Length of drop pipe 70 ft. capacity _____ g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
(Use a second sheet if needed)						
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS Signed [Signature] Date 10-2-75 Authorized representative			
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5