


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction C NW SW 1/4 1/4 1/4	Section number 13	Township number 24 T S R	Range number 15 15 W
2. Distance and direction from nearest town or city: from Macksville, Ks. 2 E - 1/2 N Street address of well location if in city:			3. Owner of well: Murfin Drilling Co. R.R. or street: 617 Union Center City, state, zip code: Wichita, Ks 67202			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile			Sketch map: 		6. Bore hole dia. 11 in. Completion date 8-15-79 Well depth 90 ft.	
5. Type and color of material			From	To	7. ☐ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
					8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☒ Other water flood	
					9. Casing: Material PVC Height: Above or below 12 in. Threaded ☐ Welded ☐ Surface 12 in. RMP ☐ PVC ☒ Weight ☐ lbs./ft. Dia. 4 1/2 in. to 90 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth Gauge No. .237	
					10. Screen: Manufacturer's name certain teed Type PVC Dia. 4 1/2 Slot 1/16 Length 20 Set between 70 ft. and 90 ft. Gravel pack? ☒ Size range of material 3/4-3/8-1/2	
top soil			0	2	11. Static water level: 31 1/2 ft. below land surface Date 8-15-79 mo./day/yr.	
clay			2	33	12. Pumping level below land surfaces: NA ft. after hrs. pumping g.p.m. ft. after hrs. pumping g.p.m. Estimated maximum yield g.p.m.	
sand and gravel			33	94	13. Water sample submitted: X Yes ☐ No Date 8-15-79 mo./day/yr.	
hard white rock			94	-	14. Well head completion: ☒ Pitless adapter 12 inches above grade	
					15. Well grouted? ☒ With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
					16. Nearest source of possible contamination: ft. 60 Direction North Type tank battery Well disinfected upon completion? HTH Yes ☐ No	
					17. Pump: ☐ Not installed Manufacturer's name Red Jacket Model number 9 BC HP 1/2 Volts 230 Length of drop pipe 63 ft. capacity 10 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)					20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosencrantz-Bemis 134 Business name License No. Address Box 713 Great Bend, Ks. Signed Freda Nadson Date 8/30/79 Authorized representative	
18. Elevation:		19. Remarks: Bl. of Agriculture # T 79-106				
Topography: ☐ Hill ☐ Slope ☐ Upland ☒ Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5